

Modification to Registration & Certification for Permits by Rule

Hilcorp Energy Company

Federal Gayette Lease Tank Battery
Galveston County, Texas
RN 102527579
Reg ID:47023

Permits by Rule Claimed: 106.352, 106.359, 106.492 & 106.512

May 2021

Prepared In Accordance With
30 TAC Chapter 106

Table of Contents

Page

SECTION 1

Introduction	1-1
Process Summary	1-1
Equipment List	1-2
Annual Emission Rates	1-3
Maximum Hourly Emission Rates	1-4
Potential Title V Applicability	1-5
Engine Compliance with National Ambient Air Quality Standards	1-6

SECTION 2: TCEQ FORMS

core data form
Table 29

SECTION 3: AIR QUALITY REQUIREMENTS

Federal Air Quality Requirements	3-1
Area Source Analysis	3-4
Permit by Rule 106.4 General Requirements	3-5
Permit by Rule 106.352 Oil & Gas Production Facility Regulation	3-10
Permit by Rule 106.492 Flare Regulations	3-11
Permit by Rule 106.512 Engine & Turbine Regulations	3-12
Reportable Emission Events	3-16
Reportable Quantity Defined	3-22
Maintenance, Startup, and Shutdown Activities	3-25

Appendix

A EMISSION CALCULATIONS

B MAPS

C SUPPORTING DOCUMENTATION

Introduction

This documentation demonstrates that the Federal Gayette Lease Tank Battery in Galveston County qualifies for an authorization under Permits by Rule 106.352, 106.359, & 106.512. This site is located approximately 8.92 miles southeast of League City, TX located in Galveston County [Lat. = 29° 23' 9.41"; Long. = -95° 2' 39.83"- (1983 Datum)]. This documentation has been prepared in accordance with 30 TAC Chapter 106.


- 1) FIN: 12-19-ICE-ES (gas compressor) has been removed from the PBR.
- 2) FINs: 13-21-GR-BS (glycol burner), 14-21-GR-SC (glycol still-column), 15-21-ICE-ES (gas compressor) and 16-21-BV (blowcase vessel) have been added to the PBR.

Process Summary

The Gayette facility is an oil and gas production facility that produces hydrocarbons from natural gas reservoirs through deep wells. Production is routed to a separator. Gas from the separator is routed to the dehy before being compressed and sent offsite for sales. Oil and water from the separator are routed to a heater treater. Gas from the heater treater is compressed and routed offsite for sales or used for gas-lift purposes. Oil from the heater treater is routed to on-site tanks for storage and subsequently hauled offsite by tank truck for sales. Produced water is routed to another facility for disposal. Vapors from the crude oil and produced water storage tanks will be vented to a continuously burning flare for controlling emissions. The flare's pilot will be fueled propane stored on-site.

Simplified Process Flow Diagram

Hilcorp Energy Company
Federal Gayette Lease Tank Battery
Galveston County, TX



**Hilcorp Energy Company
Federal Gayette Lease Tank Battery
Galveston County, TX**

EQUIPMENT LIST

Emission Point ID:	PBR:	Footnote:	Emission Point Description:	Construction Date:	Routes To:	Operating Rate/Capacity	Operating Schedule:			Reduced Emission(s)?	
							Hrs/Day or (Hrs/Yr)	Days/Wk	Wks/Yr	Yes	No
T1	106.352	a	400 bbl Crude Oil Storage Tank	Prior to 8/23/2011	T1	13,505 BOPY	24	7	52.143		✓
T2	106.352	a	400 bbl Crude Oil Storage Tank	Prior to 8/23/2011	T2	54,750 BWPY	24	7	52.143		✓
FLARE	106.492		Process Flare Pilot Gas	Prior to 2014	FLARE	N/A	24	7	52.143		✓
TRUCKLOAD	106.352		Truckloading	Prior to 2014	TRUCKLOAD	13,505 BOPY	(71)	-	-		✓
FUGITIVES	106.352		Site-Wide Fugitives	Prior to 2014	FUGITIVES	N/A	24	7	52.143		✓
11-13-MSS	106.359		Site-Wide MSS Emissions	Prior to 2014	11-13-MSS	b	-	-	-		✓
13-21-GR-BS	106.352		500 MMBTU/Hr Glycol Regenerator-Burner Stack	Prior to 2022	13-21-GR-BS	500 MBTU/Hr	24	7	52.143		✓
14-21-GR-SC	106.352		Glycol Regenerator-Still Column	Prior to 2022	14-21-GR-SC	N/A	24	7	52.143		✓
15-21-ICE-ES	106.512	c	Internal Combustion Engine-Exhaust Stack (Caterpillar G3306; Gas Compressor)	11/04/2007	15-21-ICE-ES	203 HP	24	7	52.143	✓	
16-21-BV	106.352		Blowcase Vessel (Compressor Skid Fluids)	Prior to 2022	16-21-BV	29,200 Gallon/Yr	24	7	52.143		✓

Footnotes:

- a** Vapors are routed to the control flare (FLARE) for combustion.
- b** Operating schedule varies with activity.
- c** Date refers to manufacturers date.

**Hilcorp Energy Company
Federal Gayette Lease Tank Battery
Galveston County, TX**

Maximum Annual Emission Rates

Emission Point ID:	Footnote:	Emission Point Description:	Criteria Pollutant Potential Emission Rate (Tons/Yr):						H2S
			PM ₁₀	PM _{2.5}	SO ₂	NO _x	CO	VOC	
T1		400 bbl Crude Oil Storage Tank	0.00	0.00	0.00	0.00	0.00	0.07	0.00
T2		400 bbl Crude Oil Storage Tank	0.00	0.00	0.00	0.00	0.00	0.07	0.00
FLARE		Process Flare Pilot Gas	0.00	0.00	0.00	0.12	0.24	1.07	0.00
TRUCKLOAD		Truckloading	0.00	0.00	0.00	0.00	0.00	0.14	0.00
FUGITIVES		Site-Wide Fugitives	0.00	0.00	0.00	0.00	0.00	0.87	0.00
11-13-MSS		Site-Wide MSS Emissions	0.00	0.00	0.00	0.00	0.00	0.87	0.00
13-21-GR-BS	a	500 MMBTU/Hr Glycol Regenerator-Burner Stack	0.02	0.02	0.00	0.22	0.19	0.01	0.00
14-21-GR-SC		Glycol Regenerator-Still Column	0.00	0.00	0.00	0.00	0.00	1.40	0.00
15-21-ICE-ES		Internal Combustion Engine-Exhaust Stack (Caterpillar G3306; Gas Compressor)	0.14	0.14	0.00	0.98	5.88	0.51	0.00
16-21-BV		Blowcase Vessel (Compressor Skid Fluids)	0.00	0.00	0.00	0.00	0.00	0.15	0.00
CRITERIA POLLUTANT TOTALS:			0.16	0.16	0.00	1.32	6.31	5.16	0.00

Footnotes:

a --- Operating schedule varies with activity.

TOXIC & HAZARDOUS AIR POLLUTANT TOTALS

Non-VOC HAP/TAP:	Annual Rate (TPY):	VOC HAP/TAP:	Annual Rate (TPY):
-	-	Acetaldehyde	0.02
-	-	Acrolein	0.02
-	-	Benzene	0.04
-	-	Formaldehyde	0.29
-	-	N-Hexane	0.26
-	-	Methanol	0.01
-	-	Toluene	0.01
Subtotal:	0.00	Subtotal:	0.65
HAP/TAP TOTAL:		0.65	

**Hilcorp Energy Company
Federal Gayette Lease Tank Battery
Galveston County, TX**

Maximum Hourly Emission Rates

Emission Point ID:	Footnote:	Emission Point Description:	Criteria Pollutant Potential Emission Rate (Lbs/Hr):						H2S
			PM ₁₀	PM _{2.5}	SO ₂	NO _x	CO	VOC	
T1		400 bbl Crude Oil Storage Tank	0.00	0.00	0.00	0.00	0.00	0.03	0.00
T2		400 bbl Crude Oil Storage Tank	0.00	0.00	0.00	0.00	0.00	0.03	0.00
FLARE		Process Flare Pilot Gas	0.00	0.00	0.00	0.03	0.06	0.24	0.00
TRUCKLOAD		Truckloading	0.00	0.00	0.00	0.00	0.00	5.92	0.00
FUGITIVES		Site-Wide Fugitives	0.00	0.00	0.00	0.00	0.00	0.20	0.00
11-13-MSS	a	Site-Wide MSS Emissions	0.00	0.00	0.00	0.00	0.00	0.20	0.00
13-21-GR-BS		500 MMBTU/Hr Glycol Regenerator-Burner Stack	0.00	0.00	0.00	0.05	0.04	0.00	0.00
14-21-GR-SC		Glycol Regenerator-Still Column	0.00	0.00	0.00	0.00	0.00	0.32	0.00
15-21-ICE-ES		Internal Combustion Engine-Exhaust Stack (Caterpillar G3306; Gas Compressor)	0.03	0.03	0.00	0.22	1.34	0.12	0.00
16-21-BV		Blowcase Vessel (Compressor Skid Fluids)	0.00	0.00	0.00	0.00	0.00	0.07	0.00
CRITERIA POLLUTANT TOTALS:			0.03	0.03	0.00	0.30	1.44	7.13	0.00

Footnotes:

a --- Operating schedule varies with activity.

TOXIC & HAZARDOUS AIR POLLUTANT TOTALS

Non-VOC HAP/TAP:	Maximum Rate (Lb/Hr):	VOC HAP/TAP:	Maximum Rate (Lb/Hr):
-	-	<i>Benzene</i>	0.01
-	-	<i>Ethylbenzene</i>	0.00
-	-	<i>Formaldehyde</i>	0.07
-	-	<i>N-Hexane</i>	0.06
-	-	<i>Toluene</i>	0.00
-	-	<i>Xylenes (mixed isomers)</i>	0.00
Subtotal:	0.00	Subtotal:	0.14
HAP/TAP TOTAL:		0.14	

**Federal Gayette Lease Tank Battery
Hilcorp Energy Company
Galveston County, TX**

POTENTIAL TITLE V APPLICABILITY

The following table will list all sites under common control and that are contiguous except for intervening road, railroad, right-of-way, or the like and that are located less than 1/4 mile apart and dependent on each other.

Contiguous Sites	PM	SO₂	NO_x	CO	VOC	Total HAP
Federal Gayette Lease Tank Battery	0.16	0.00	1.32	6.31	5.16	0.65
TOTALS	0.16	0.00	1.32	6.31	5.16	0.65
Major Source Thresholds for Galveston County	100	100	100	100	100	25

The above table indicates that a Title V federal operating permit is not required.

Engine Compliance with National Ambient Air Quality Standards

The site is located in Galveston County which is located in TCEQ Region 12. According to data provided by TCEQ, the NO₂ background concentration is 75 µg/m³. In accordance with 30 TAC 106.512 paragraph 6, the internal combustion engine at this site will demonstrate compliance using method A (via EPA SCREEN3 dispersion model). The appropriate NO₂ to NO_x ratio to be applied is checked below:

Gas Compressor Engine (FIN: 15-21-ICE-ES)

Figure 1: 30 TAC 106.512(6)(A)			
Device	Q = NO _x emission rate (g/hp-hr)	NO ₂ / NO _x ratio	applicable
IC engine	less than 2.0	0.4	
IC engine	2.0 thru 10.0	0.15 + (0.5/Q)	
IC engine	greater than 10.0	0.2	
Turbine		0.25	
Engine w/catalytic converter		0.85	✓

Engine Data					amb. temp (°F)	receptor ht (ft)
NOx (lb/hr)	stack ht (ft)	stk dia (in)	exit (ft/sec)	exit (°F)		
0.2238	15	6	82.59	1004	75	20
EPA SCREEN3 MODEL						
source	rate (g/s)	stack ht (M)	stack dia (M)	vel (M/S)	stk temp (K)	amb tmp (K)
point	0.03	4.57	0.15	25.18	813	297
recep ht (M)	urban/rural	downwash	complex	simple	meterology	auto
1.5	R	N	N	Y	Full	Y
terrain height above stack base (M)			min & max grid distance (M)			
0						
			10		300	
Results (highest µg/m³) (1 hr avg)			NO₂ / NOx ratio			
12.34			0.85			
Background µg/m³ (1 hour avg)			NO₂ µg/m³ (1 hour avg)		NO₂ NAAQS (1 hour avg)	
75			85		188	

The NO₂ level of 15-21-ICE-ES is 10.49 µg/m³ and when the background concentration is added the resultant NO₂ level is 85.49 µg/m³. Since this is less than the NAAQS of 188 µg/m³, compliance is therefore demonstrated. The SCREEN3 program results along with TCEQ supporting documentation is contained in Appendix C.



TCEQ Core Data Form

TCEQ Use Only

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)		
<input type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)	<input checked="" type="checkbox"/> Other Certification of Emission Limits	
2. Customer Reference Number (if issued)	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number (if issued)
CN 600125991		RN 102527579

SECTION II: Customer Information

4. General Customer Information		5. Effective Date for Customer Information Updates (mm/dd/yyyy)			
<input checked="" type="checkbox"/> New Customer <input type="checkbox"/> Update to Customer Information <input type="checkbox"/> Change in Regulated Entity Ownership					
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)					
<i>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</i>					
6. Customer Legal Name (If an individual, print last name first: e.g.: Doe, John)				If new Customer, enter previous Customer below:	
Hilcorp Energy Company					
7. TX SOS/CPA Filing Number		8. TX State Tax ID (11 digits)		9. Federal Tax ID (9 digits)	
11. Type of Customer:		<input type="checkbox"/> Corporation		<input type="checkbox"/> Individual	
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> Other		<input type="checkbox"/> Sole Proprietorship		Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited	
12. Number of Employees		<input type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input checked="" type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher		13. Independently Owned and Operated?	
				<input type="checkbox"/> Yes <input type="checkbox"/> No	
14. Customer Role (Proposed or Actual) - as it relates to the Regulated Entity listed on this form. Please check one of the following:					
<input type="checkbox"/> Owner <input type="checkbox"/> Operator <input checked="" type="checkbox"/> Owner & Operator					
<input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> Voluntary Cleanup Applicant <input type="checkbox"/> Other:					
15. Mailing Address:					
1111 Travis Street					
City		Houston		State	
		TX		ZIP	
				77002	
				ZIP + 4	
16. Country Mailing Information (if outside USA)				17. E-Mail Address (if applicable)	
				mvicenik@hilcorp.com	
18. Telephone Number		19. Extension or Code		20. Fax Number (if applicable)	
(713) 209 - 2400				(713) 209 - 2401	

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If "New Regulated Entity" is selected below this form should be accompanied by a permit application)	
<input type="checkbox"/> New Regulated Entity <input type="checkbox"/> Update to Regulated Entity Name <input checked="" type="checkbox"/> Update to Regulated Entity Information	
<i>The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).</i>	
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)	
Federal Gayette Lease Tank Battery	

23. Street Address of the Regulated Entity: (No PO Boxes)								
	City		State		ZIP		ZIP + 4	
24. County	Galveston							

Enter Physical Location Description if no street address is provided.

25. Description to Physical Location:	REGUATED ENTITY LOCATION: FROM INTX HIGHWAY 6 & JACK BROOKS RD GO N ON JACK BROOKS RD APPROX 1.5 MI TO FACILITY ON L							
26. Nearest City					State		Nearest ZIP Code	
Alta Loma					TX		77568	
27. Latitude (N) In Decimal:		29.385948		28. Longitude (W) In Decimal:		-95.044396		
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds			
29	23	9.41	-95	2	39.83			
29. Primary SIC Code (4 digits)		30. Secondary SIC Code (4 digits)		31. Primary NAICS Code (5 or 6 digits)		32. Secondary NAICS Code (5 or 6 digits)		
1311				211120				

33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)

Oil & Gas Production

34. Mailing Address:	1111 Travis Street							
	City	Houston	State	TX	ZIP	77098	ZIP + 4	
35. E-Mail Address:		mvicenik@hilcorp.com						
36. Telephone Number			37. Extension or Code		38. Fax Number (if applicable)			
(713) 209 - 2400					() -			

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input checked="" type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
	Reg ID - 47023			
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Waste Water	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

SECTION IV: Preparer Information

40. Name: Nicholas Fitzmorris, P.E.		41. Title: Project Manager	
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address
(337) 839 - 1075	223	(337) 839 - 1072	nfitzmorris@hlpengineering.com

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Hilcorp Energy Company	Job Title:	Environmental Manager
Name (In Print):	Matt Vicenik	Phone:	(713) 209 - 2400
Signature:		Date:	



Texas Commission on Environmental Quality
Table 29 Reciprocating Engines

I. Engine Data											
Manufacturer: Caterpillar			Model No. G3306			Serial No.			Manufacture Date: 11/4/2007		
Rebuilds Date: N/A			No. of Cylinders: 6			Compression Ratio: 8:1			EPN: 15-21-ICE		
Application: <input checked="" type="checkbox"/> Gas Compression <input type="checkbox"/> Electric Generation <input type="checkbox"/> Refrigeration <input type="checkbox"/> Emergency/Stand by											
<input checked="" type="checkbox"/> 4 Stroke Cycle <input type="checkbox"/> 2 Stroke Cycle <input type="checkbox"/> Carbureted <input type="checkbox"/> Spark Ignited <input type="checkbox"/> Dual Fuel <input type="checkbox"/> Fuel Injected											
<input type="checkbox"/> Diesel <input type="checkbox"/> Naturally Aspirated <input type="checkbox"/> Blower /Pump Scavenged <input type="checkbox"/> Turbo Charged and I.C. <input type="checkbox"/> Turbo Charged											
<input type="checkbox"/> Intercooled <input type="checkbox"/> I.C. Water Temperature <input type="checkbox"/> Lean Burn <input checked="" type="checkbox"/> Rich Burn											
Ignition/Injection Timing: Fixed:						Variable:					
Manufacture Horsepower Rating: 203						Proposed Horsepower Rating: 203					
Discharge Parameters											
Stack Height (Feet)			Stack Diameter (Feet)			Stack Temperature (°F)			Exit Velocity (FPS)		
15			0.5			1004			82.59		
II. Fuel Data											
Type of Fuel: <input checked="" type="checkbox"/> Field Gas <input type="checkbox"/> Landfill Gas <input type="checkbox"/> LP Gas <input type="checkbox"/> Natural Gas <input type="checkbox"/> Digester Gas <input type="checkbox"/> Diesel											
Fuel Consumption (BTU/bhp-hr):7877				Heat Value: (HHV)				(LHV)			
Sulfur Content (grains/100 scf - weight %):											
III. Emission Factors (Before Control)											
NO_x		CO		SO₂		VOC		Formaldehyde		PM10	
g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv
27.71		1.5		0.00		0.26		0.16			
Source of Emission Factors: <input checked="" type="checkbox"/> Manufacturer Data <input type="checkbox"/> AP-42 <input type="checkbox"/> Other (specify):											
IV. Emission Factors (Post Control)											
NO_x		CO		SO₂		VOC		Formaldehyde		PM10	
g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv
0.5		3.0		0.00		0.26		0.16			
Method of Emission Control: <input checked="" type="checkbox"/> NSCR Catalyst <input type="checkbox"/> Lean Operation <input type="checkbox"/> Parameter Adjustment											
<input type="checkbox"/> Stratified Charge <input type="checkbox"/> JLCC Catalyst <input type="checkbox"/> Other (Specify):											
<i>Note: Must submit a copy of any manufacturer control information that demonstrates control efficiency.</i>											
Is Formaldehyde included in the VOCs?										<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
V. Federal and State Standards (Check all that apply)											
<input type="checkbox"/> NSPS JJJJ <input type="checkbox"/> MACT ZZZZ <input type="checkbox"/> NSPS IIII <input checked="" type="checkbox"/> Title 30 Chapter 117 - List County: <u>Galveston</u>											
VI. Additional Information											
1. Submit a copy of the engine manufacturer's site rating or general rating specification data. 2. Submit a typical fuel gas analysis, including sulfur content and heating value. For gaseous fuels, provide mole percent of constituents. 3. Submit description of air/fuel ratio control system (manufacturer information is acceptable).											

AIR QUALITY REQUIREMENTS

40 CFR 60 Subpart K, Ka and Kb - Standards for Storage Vessels for Petroleum Liquids.

DOES NOT APPLY: The tanks are prior to lease custody transfer and the storage capacity of each is less than 10,000 bbls.

40 CFR Part 60-Subpart JJJJ - National Emission Standards for Hazardous Air Pollutants

40 CFR 60.4230(a)(3)(iii) & (a)(5) - DOES NOT APPLY: The gas compressor engine (FIN: 15-21-ICE) at this site was not manufactured on or after July 1, 2008 and has not been modified or reconstructed since June 12, 2006.

40 CFR Part 60 Subpart OOOO - Standards of Performance for Crude Oil and Natural Gas Production, Transmission, and Distribution

40 CFR 60.5360 - Storage tanks at this facility were constructed prior to August 23, 2011.

40 CFR 60.5365(d) - Pneumatic controllers at this site are not continuous bleed natural gas-driven pneumatic controllers.

The gas compressor is located at a wellsite and is not an affected facility under this subpart.

40 CFR Part 63 Subpart ZZZZ - Reciprocating Internal Combustion Engines MACT Standard.

This site would not be classified as a major source of Hazardous Air Pollutants. FIN: 15-21-ICE meets the requirements of this subpart by meeting the requirements of 40 CFR 60-Subpart JJJJ.

40 CFR Part 60 Subpart OOOOa - Standards of Performance for Crude Oil and Natural Gas Production, Transmission, and Distribution

40 CFR 60.5360a(e) – DOES NOT APPLY: The storage tanks at this facility were constructed prior to 9/18/2015 and therefore are not affected facilities under this subpart.

40 CFR 60.5365a(d) - Pneumatic controllers at this site were constructed prior to 9/18/2015 and is not affected under this subpart.

The gas compressor is located at a wellsite and is not an affected facility under this subpart.

The wellsite has not commenced construction, modification or reconstruction and not an affected facility under this subpart.

40 CFR Part 64 - Compliance Assurance Monitoring

DOES NOT APPLY: This site should be classified as a minor source under the Part 70 permitting program, considering the existing control measures.

40 CFR Part 70 - State Operating Permit Programs

DOES NOT APPLY: This site would not be classified as a "major" source under this program, considering the existing control measures.

30 TAC §101.10 - Emissions Inventory Requirements

The owner/operator of a regulated entity should keep annual emissions inventories (due by March 31st for the previous calendar year) if actual emissions exceed the reporting threshold.

30 TAC §101.201 - Emissions Event Reporting and Recordkeeping Requirements

The owner/operator of a regulated entity should keep records of any applicable emissions events and notify TCEQ of the event as specified in this section.

30 TAC §106.359 - Planned Maintenance, Startup, and Shutdown (MSS) at Oil and Gas Handling and Production Facilities

106.359(a) - This section authorizes emissions from planned mss facilities and activities, and any associated emission capture and control facilities.

106.359(d) - Best Management Practices - each permit holder should establish, implement, and update, as appropriate, a program to maintain and repair facilities. Record of conducted planned MSS activities should be kept.

30 TAC §106.8 - Recordkeeping

Owners and operators of sites authorized under a Permit by Rule (PBR) must keep a copy of each PBR and all applicable conditions and requirements at the site. The owner/operator must also keep records demonstrating compliance with any general and/or PBR conditions.

30 TAC §106.352 - Oil & Gas Facilities

106.352(2) - This site operates as an oil & gas production operation which handles gases and liquids associated with the production and processing of fluids found in geologic formations beneath the earth's surface whose total emissions do not exceed the thresholds of this program as demonstrated herein.

30 TAC §106.492 - Flares (FIN: FLARE)

106.492 (1) - The flare at this site meets the design requirements for tip velocity and heat release as specified in this section (refer to calculations in Appendix C). Also note that this flare is equipped with an automatic ignition system and does not emit any reduced sulfur compounds.

106.492 (2) - The gas stream burned by this flare has a lower heating value greater than 200 BTU/ft³. This flare does not burn sulfur, chlorine, or compounds of either element. No liquids are burned in the flare.

30 TAC §106.512 - Engines and Turbines

106.512 (1) - The gas compressor engine (FIN: 15-21-ICE), is rated at less than 240 horsepower and does not require registration with the Office of Permitting, Remediation, and Registration in Austin.

106.512 (5) - Fuel gas should not contain more than ten grains of total sulfur per 100 dry standard cubic feet. If using field gas that contains more than 1.5 grains of H₂S or 30 grains of sulfur per 100 scf, the engine owner/operator should maintain records that document quarterly hydrogen sulfide and total sulfur content and demonstrate that SO₂ emissions do not exceed 25 tons per year.

106.512 (6) - Compliance with the National Ambient Air Quality Standard (NAAQS) is demonstrated in this application by use of dispersion modeling.

30 TAC §111.111(a)(4) - Flare

Visible emissions from process gas flare shall not be permitted for more than five minutes in any two hour period, except during periods of upset as defined in §101.11(a).

(i) Anytime there is an operational change in the flare that requires a permit amendment, compliance shall be determined using Method 22, Method 9 or an alternate test method approved by the executive director and EPA. The observation period for this compliance demonstration shall be no less than two hours unless noncompliance is determined in a shorter time period or operational changes are made to the flare that stop any observed smoking; and

(ii) by a daily notation in the flare operation log that the flare was observed including the time of day and whether or not the flare was smoking. The flare operator shall record at least 98% of these required observations. If smoking is detected, compliance with the emission limits shall be determined using Method 22, Method 9, or an alternate test approved by the executive director and EPA.

30 TAC §117.2000 - Combustion Control at Minor Sources in Ozone Nonattainment Areas

117.2010 - This site is located in the Houston-Galveston-Brazoria Ozone Nonattainment Area and the stationary, reciprocating internal combustion engine (FIN: 15-21-ICE) at this site must meet the NO_x emission limit of 0.5 g/hp-hr and the CO emission limit of 3.0 g/hp-hr.

117.2030 - This engine is controlled using nonselective catalytic reduction and must also be equipped with an automatic air-fuel ratio (AFR) controller.

117.2035 - MONITORING : The owner/operator of each unit subject to §117.2010 of this title (relating to Emission Specifications) and subject to Chapter 101, Subchapter H, Division 3 of this title (relating to Mass Emissions Cap and Trade Program) shall install, calibrate, maintain, and operate totalizing fuel flow meters with an accuracy of ±5%, to individually and continuously measure the gas and liquid fuel usage. [A computer that collects, sums, and stores electronic data from continuous fuel flow meters in an acceptable totalizer. For the purpose of compliance with this subsection for units having pilot fuel supplied by a separate fuel system or from an unmonitored portion of the same fuel system, the fuel flow to pilots may be calculated using the manufacturer's design flow rates rather than measured with a fuel flow meter. The calculated pilot fuel flow rate must be added to the monitored fuel flow when fuel flow is totalized.]

117.2035 - TESTING: The owner/operator of the engine must conduct an initial engine stack test with measure NO_x, CO, and O₂ emissions. The stack test must be conducted within 60 days following initial engine start-up to verify that actual emission rates are in compliance with the limits established in this PBR. Retesting is required within 60 days after any modification that could reasonably be expected to increase NO_x emissions.

117.2045 - The owner or operator shall maintain written or electronic records of annual fuel usage, NO_x and CO emission measurements, catalytic converter, AFR, or other emissions-related control system maintenance, including the date and nature of corrective actions taken, initial engine stack test, and daily average horsepower for at least five years.

Hilcorp Energy Company - Federal Gayette Lease Tank Battery				
Area Source Analysis - General Requirements 40 CFR 63.1(b)(3) and 63.10(b)(3)				
<i>Process</i>	<i>Potential (Uncontrolled) Toxic Totals (TPY)</i>	<i>Highest Potential (Uncontrolled) Toxic Substances (TPY)</i>	<i>Toxic Totals (Federally Enforceable)</i>	<i>Single Highest (Fed. Enf.) Toxic/Amount in TPY</i>
Glycol Dehydration	0.00	N-Hexane/0.00	0.00	N-Hexane/0.00
Storage Tanks	N/A	N/A	N/A	N/A
Combustion Turbines	N/A	N/A	N/A	N/A
Reciprocating Internal Combustion Engines	0.41	Formaldehyde/0.29;	0.41	Formaldehyde/0.29;
TOTALS:	0.41	Formaldehyde/0.29	0.41	Formaldehyde/0.29

Facility Type: Oil and Gas Production
SICC: 1311

Based on the values above, resulting from the potential throughput rates and/or the operational limits reflected in this application and to be established within this authorization, this site is determined to be an area source of HAP under this program.

Permit by Rule 106.4 General Requirements

§106.4. Requirements for Permitting by Rule.

(a) To qualify for a permit by rule, the following general requirements must be met.

(1) Total actual emissions authorized under permit by rule from the facility shall not exceed 250 tons per year (tpy) of carbon monoxide (CO) or nitrogen oxides (NO_x); or 25 tpy of volatile organic compounds (VOC) or sulfur dioxide (SO₂) or inhalable particulate matter (PM₁₀); or 25 tpy of any other air contaminant except carbon dioxide, water, nitrogen, methane, ethane, hydrogen, and oxygen.

(2) Any facility or group of facilities, which constitutes a new major stationary source, as defined in §116.12 of this title (relating to Nonattainment Review Definitions), or any modification which constitutes a major modification, as defined in §116.12 of this title, under the new source review requirements of the Federal Clean Air Act (FCAA), Part D (Nonattainment) as amended by the FCAA Amendments of 1990, and regulations promulgated thereunder, must meet the permitting requirements of Chapter 116, Subchapter B of this title (relating to New Source Review Permits) and cannot qualify for a permit by rule under this chapter. Persons claiming a permit by rule under this chapter should see the requirements of §116.150 of this title (relating to New Major Source or Major Modification in Ozone Nonattainment Areas) to ensure that any applicable netting requirements have been satisfied.

(3) Any facility or group of facilities, which constitutes a new major stationary source, as defined in 40 Code of Federal Regulations (CFR) §52.21, or any change which constitutes a major modification, as defined in 40 CFR §52.21, under the new source review requirements of the FCAA, Part C (Prevention of Significant Deterioration) as amended by the FCAA Amendments of 1990, and regulations promulgated thereunder, must meet the permitting requirements of Chapter 116, Subchapter B of this title and cannot qualify for a permit by rule under this chapter.

(4) Unless at least one facility at an account has been subject to public notification and comment as required in Chapter 116, Subchapter B or Subchapter D of this title (relating to New Source Review Permits or Permit Renewals), total actual emissions from all facilities permitted by rule at an account shall not exceed 250 tpy of CO or NO_x; or 25 tpy of VOC or SO₂ or PM₁₀; or 25 tpy of any other air contaminant except carbon dioxide, water, nitrogen, methane, ethane, hydrogen, and oxygen.

(5) Construction or modification of a facility commenced on or after the effective date of a revision of this section or the effective date of a revision to a specific permit by rule in this chapter must meet the revised requirements to qualify for a permit by rule.

(6) A facility shall comply with all applicable provisions of the FCAA, §111 (Federal New Source Performance Standards) and §112 (Hazardous Air Pollutants), and the new source review requirements of the FCAA, Part C and Part D and regulations promulgated thereunder.

(7) There are no permits under the same commission account number that contain a condition or conditions precluding the use of a permit by rule under this chapter.

(8) The proposed facility or group of facilities shall obtain allowances for NO_x if they are subject to Chapter 101, Subchapter H, Division 3 of this title (relating to Mass Emissions Cap and Trade Program).

(b) No person shall circumvent by artificial limitations the requirements of §116.110 of this title

(relating to Applicability).

(c) The emissions from the facility shall comply with all rules and regulations of the commission and with the intent of the TCAA, including protection of health and property of the public, and all emissions control equipment shall be maintained in good condition and operated properly during operation of the facility.

(d) Facilities permitted by rule under this chapter are not exempted from any permits or registrations required by local air pollution control agencies. Any such requirements must be in accordance with TCAA, §382.113 and any other applicable law.

Adopted March 7, 2001

Effective March 29, 2001

§106.6. Registration of Emissions.

(a) An owner or operator may certify and register the maximum emission rates from facilities permitted by rule under this chapter in order to establish federally-enforceable allowable emission rates which are below the emission limitations in §106.4 of this title (relating to Requirements for Permitting by Rule).

(b) All representations with regard to construction plans, operating procedures, and maximum emission rates in any certified registration under this section become conditions upon which the facility permitted by rule shall be constructed and operated.

(c) It shall be unlawful for any person to vary from such representation if the change will cause a change in the method of control of emissions, the character of the emissions, or will result in an increase in the discharge of the various emissions, unless the certified registration is first revised.

(d) The certified registration must include documentation of the basis of emission estimates and a written statement by the registrant certifying that the maximum emission rates listed on the registration reflect the reasonably anticipated maximums for operation of the facility.

(e) Certified registrations used to demonstrate that Chapter 122 of this title (relating to Federal Operating Permits) does not apply to a source shall be submitted on the required form to the executive director; to the appropriate commission regional office; and to all local air pollution control agencies having jurisdiction over the site.

(1) Certified registrations established prior to the effective date of this rule shall be submitted on or before February 3, 2003.

(2) Certified registrations established on or after the effective date of this rule shall be submitted no later than the date of operation.

(f) All certified registrations shall be maintained on-site and be provided immediately upon request by representatives of the commission or any local air pollution control agency having jurisdiction over the site. If however, the site normally operates unattended, certified registrations and records demonstrating compliance with the certified registration must be maintained at an office within Texas having day-to-day operational control of the site. Upon request, the commission shall make any such records of compliance available to the public in a timely manner.

(g) Copies of certified registrations shall be included in permit applications subject to review under Chapter 116, Subchapter B of this title (relating to New Source Review Permits).

§106.8. Recordkeeping

(a) Owners or operators of facilities and sources that are de minimis as designated in §116.119 of this title (relating to De Minimis Facilities or Sources) are not subject to this section.

(b) Owners or operators of facilities operating under a permit by rule (PBR) in Subchapter C of this chapter (relating to Domestic and Comfort Heating and Cooling) or under those PBRs that only name the type of facility and impose no other conditions in the PBR itself do not need to comply with specific recordkeeping requirements of subsection (c) of this section. A list of these PBRs will be available through the commission's Austin central office, regional offices, and the commission's website. Upon request from the commission or any air pollution control program having jurisdiction, claimants must provide information that would demonstrate compliance with §106.4 of this title (relating to Requirements for Permitting by Rule), or the general requirements, if any, in effect at the time of the claim, and the PBR under which the facility is authorized.

(c) Owners or operators of all other facilities authorized to be constructed and operate under a PBR must retain records as follows:

(1) maintain a copy of each PBR and the applicable general conditions of §106.4 of this title or the general requirements, if any, in effect at the time of the claim under which the facility is operating. The PBR and general requirements claimed should be the version in effect at the time of construction or installation or changes to an existing facility, whichever is most recent. The PBR holder may elect to comply with a more recent version of the applicable PBR and general requirements;

(2) maintain records containing sufficient information to demonstrate compliance with the following:

(A) all applicable general requirements of §106.4 of this title or the general requirements, if any, in effect at the time of the claim; and

(B) all applicable PBR conditions;

(3) keep all required records at the facility site. If however, the facility normally operates unattended, records must be maintained at an office within Texas having day-to-day operational control of the plant site;

(4) make the records available in a reviewable format at the request of personnel from the commission or any air pollution control program having jurisdiction;

(5) beginning April 1, 2002, keep records to support a compliance demonstration for any consecutive 12-month period. Unless specifically required by a PBR, records regarding the quantity of air contaminants emitted by a facility to demonstrate compliance with §106.4 of this title prior to April 1, 2002 are not required under this section; and

(6) for facilities located at sites designated as major in accordance with §122.10(13) of this title (relating to General Definitions) or subject to or potentially subject to any applicable federal requirement, retain all records demonstrating compliance for at least five years. For facilities located at all other sites, all records demonstrating compliance must be retained for at least two years. These

record retention requirements supercede any retention conditions of an individual PBR.

Adopted October 10, 2001

Effective November 1, 2001

§106.13. References to Standard Exemptions and Exemptions from Permitting.

The authorizations formerly known as standard exemptions and exemptions from permitting are referred to as permits by rule in this title. Types of facilities and changes within facilities authorized by those standard exemptions and exemptions from permitting continue to be authorized unless modifications or changes to those facilities has caused them to no longer meet the conditions of the former standard exemption or exemption from permitting and the general requirements of this subchapter.

Adopted August 9, 2000

Effective September 4, 2000

§106.50 Registration Fees for Permits by Rule

(a) A registrant who submits a permit by rule (PBR) registration for review by the commission shall remit one of the following fees with the PI-7 registration form:

(1) \$100 for:

(A) small businesses, as defined in Texas Government Code, §2006.001;

(B) non-profit organizations; and

(C) municipalities, counties, and independent school districts with populations or districts of 10,000 or fewer residents, according to the most recently published census; or

(2) \$450 for all other entities.

(b) This fee does not apply to:

(1) a certification submitted solely for the purpose of establishing a federally enforceable emissions limit under §106.6 of this title (relating to Registration of Emissions);

(2) a remediation project conducted under §106.533 of this title (relating to Remediation); or

(3) resubmittal of previously reviewed registrations, if received within six months of a written response on the original action.

(c) This fee is for PBR registrations that are received on or after November 1, 2002.

(d) All PBR fees will be remitted in the form of a check, certified check, electronic funds transfer, or money order made payable to the Texas Commission on Environmental Quality (TCEQ) and submitted concurrently with the registration to the TCEQ, P.O. Box 13088, MC 214, Austin, Texas 78711-3087. No fees will be refunded.

PBR 106.352 - Oil & Gas Production Facility Regulation
§106.352. Oil and Gas Production Facilities.

Any oil or gas production facility, carbon dioxide separation facility, or oil or gas pipeline facility consisting of one or more tanks, separators, dehydration units, free water knockouts, gunbarrels, heater treaters, natural gas liquids recovery units, or gas sweetening and other gas conditioning facilities, including sulfur recovery units at facilities conditioning produced gas containing less than two long tons per day of sulfur compounds as sulfur are permitted by rule, provided that the following conditions of this section are met. This section applies only to those facilities named which handle gases and liquids associated with the production, conditioning, processing, and pipeline transfer of fluids found in geologic formations beneath the earth's surface.

(1) Compressors and flares shall meet the requirements of §106.512 and §106.492 of this title (relating to Stationary Engines and Turbines, and Flares).

(2) Total emissions, including process fugitives, combustion unit stacks, separator, or other process vents, tank vents, and loading emissions from all such facilities constructed at a site under this section shall not exceed 25 tons per year (tpy) each of sulfur dioxide (SO₂), all other sulfur compounds combined, or all volatile organic compounds (VOC) combined; and 250 tpy each of nitrogen oxide and carbon monoxide. Emissions of VOC and sulfur compounds other than SO₂ must include gas lost by equilibrium flash as well as gas lost by conventional evaporation.

(3) Any facility handling sour gas shall be located at least 1/4 mile from any recreational area or residence or other structure not occupied or used solely by the owner or operator of the facility or the owner of the property upon which the facility is located.

(4) Total emissions of sulfur compounds, excluding sulfur oxides, from all vents shall not exceed 4.0 pounds per hour (lb/hr) and the height of each vent emitting sulfur compounds shall meet the following requirements, except in no case shall the height be less than 20 feet:

Total as Hydrogen Sulfide, lb/hr	Minimum vent height, feet
0.27	20
0.60	30
1.94	50
3.00	60
4.00	68

NOTE: Other values may be interpolated.

(5) Before operation begins, facilities handling sour gas shall be registered with the commission's Office of Permitting, Remediation, and Registration in Austin using Form PI-7 along with supporting documentation that all requirements of this section will be met. For facilities constructed under §106.353 of this title (relating to Temporary Oil and Gas Facilities), the registration is required before operation under this section can begin. If the facilities cannot meet this section, a permit under Chapter 116 of this title (relating to Control of Air Pollution by Permits for New Construction or Modification) is required prior to continuing operation of the facilities.

Adopted August 9, 2000

Effective September 4, 2000

PBR 106.492 - Flare Regulations

§106.492. Flares.

Smokeless gas flares which meet the following conditions of this section are permitted by rule:

(1) design requirements.

(A) The flare shall be equipped with a flare tip designed to provide good mixing with air, flame stability, and a tip velocity less than 60 feet per second (ft/sec) for gases having a lower heating value less than 1,000 British thermal units per cubic foot (Btu/ft³) or a tip velocity less than 400 ft/sec for gases having a lower heating value greater than 1,000 Btu/ft³.

(B) The flare shall be equipped with a continuously burning pilot or other automatic ignition system that assures gas ignition and provides immediate notification of appropriate personnel when the ignition system ceases to function. A gas flare which emits no more than 4.0 pounds per hour (lb/hr) of reduced sulfur compounds, excluding sulfur oxides, is exempted from the immediate notification requirement, provided the emission point height meets the requirements of §106.352(4) of this title (relating to Oil and Gas Production Facilities).

(C) A flare which burns gases containing more than 24 parts per million by volume (ppmv) of sulfur, chlorine, or compounds containing either element shall be located at least 1/4 mile from any recreational area or residence or other structure not occupied or used solely by the owner or operator of the flare or the owner of the property upon which the flare is located.

(D) The heat release of a flare which emits sulfur dioxide (SO₂) or hydrogen chloride (HCl) shall be greater than or equal to the following values:

$$\text{For HCl } Q = 2.73 \times 10^5 \times \text{HCl}$$

$$\text{For SO}_2 \text{ } Q = 0.53 \times 10^5 \times \text{SO}_2$$

Where Q = heat release, British thermal units per hour, based on lower heating value

HCl = HCl emission rate, lb/hr

SO₂ = SO₂ emission rate, lb/hr

(2) operational conditions.

(A) The flare shall burn a combustible mixture of gases containing only carbon, hydrogen, nitrogen, oxygen, sulfur, chlorine, or compounds derived from these elements. When the gas stream to be burned has a net or lower heating value of more than 200 Btu/ft³ prior to the addition of air, it may be considered combustible.

(B) A flare which burns gases containing more than 24 ppmv of sulfur, chlorine, or compounds containing either element shall be registered with the commission's Office of Permitting, Remediation, and Registration in Austin using Form PI-7 prior to construction of a new flare or prior to the use of an existing flare for the new service.

(C) Under no circumstances shall liquids be burned in the flare.

Adopted August 9, 2000

Effective September 4, 2000

PBR 106.512 - Engine and Turbine Regulations

§106.512. Stationary Engines and Turbines.

Gas or liquid fuel-fired stationary internal combustion reciprocating engines or gas turbines that operate in compliance with the following conditions of this section are permitted by rule.

(1) The facility shall be registered by submitting the commission's Form PI-7, Table 29 for each proposed reciprocating engine, and Table 31 for each proposed gas turbine to the commission's Office of Permitting, Remediation, and Registration in Austin within ten days after construction begins. Engines and turbines rated less than 240 horsepower (hp) need not be registered, but must meet paragraphs (5) and (6) of this section, relating to fuel and protection of air quality. Engine hp rating shall be based on the engine manufacturer's maximum continuous load rating at the lesser of the engine or driven equipment's maximum published continuous speed. A rich-burn engine is a gas-fired spark-ignited engine that is operated with an exhaust oxygen content less than 4.0% by volume. A lean-burn engine is a gas-fired spark-ignited engine that is operated with an exhaust oxygen content of 4.0% by volume, or greater.

(2) For any engine rated 500 hp or greater, subparagraphs (A) - (C) of this paragraph shall apply.

(A) The emissions of nitrogen oxides (NO_x) shall not exceed the following limits:

(i) 2.0 grams per horsepower-hour (g/hp-hr) under all operating conditions for any gas-fired rich-burn engine;

(ii) 2.0 g/hp-hr at manufacturer's rated full load and speed, and other operating conditions, except 5.0 g/hp-hr under reduced speed, 80-100% of full torque conditions, for any spark-ignited, gas-fired lean-burn engine, or any compression-ignited dual fuel-fired engine manufactured new after June 18, 1992;

(iii) 5.0 g/hp-hr under all operating conditions for any spark-ignited, gas-fired, lean-burn two-cycle or four-cycle engine or any compression-ignited dual fuel-fired engine rated 825 hp or greater and manufactured after September 23, 1982, but prior to June 18, 1992;

(iv) 5.0 g/hp-hr at manufacturer's rated full load and speed and other operating conditions, except 8.0 g/hp-hr under reduced speed, 80-100% of full torque conditions for any spark-ignited, gas-fired, lean-burn four-cycle engine, or any compression-ignited dual fuel-fired engine that:

(I) was manufactured prior to June 18, 1992, and is rated less than 825 hp; or

(II) was manufactured prior to September 23, 1982;

(v) 8.0 g/hp-hr under all operating conditions for any spark-ignited, gas-fired, two-cycle lean-burn engine that:

(I) was manufactured prior to June 18, 1992, and is rated less than 825 hp; or

(II) was manufactured prior to September 23, 1982;

(vi) 11.0 g/hp-hr for any compression-ignited liquid-fired engine.

(B) For such engines which are spark-ignited gas-fired or compression-ignited dual fuel-fired, the engine shall be equipped as necessary with an automatic air-fuel ratio (AFR) controller which maintains AFR in the range required to meet the emission limits of subparagraph (A) of this paragraph. An AFR controller shall be deemed necessary for any engine controlled with a non-selective catalytic reduction (NSCR) converter and for applications where the fuel heating value varies more than ± 50 British thermal unit/standard cubic feet from the design lower heating value of the fuel. If an NSCR converter is used to reduce NO_x , the automatic controller shall operate on exhaust oxygen control.

(C) Records shall be created and maintained by the owner or operator for a period of at least two years, made available, upon request, to the commission and any local air pollution control agency having jurisdiction, and shall include the following:

(i) documentation for each AFR controller, manufacturer's, or supplier's recommended maintenance that has been performed, including replacement of the oxygen sensor as necessary for oxygen sensor-based controllers. The oxygen sensor shall be replaced at least quarterly in the absence of a specific written recommendation;

(ii) documentation on proper operation of the engine by recorded measurements of NO_x and carbon monoxide (CO) emissions as soon as practicable, but no later than seven days following each occurrence of engine maintenance which may reasonably be expected to increase emissions, changes of fuel quality in engines without oxygen sensor-based AFR controllers which may reasonably be expected to increase emissions, oxygen sensor replacement, or catalyst cleaning or catalyst replacement. Stain tube indicators specifically designed to measure NO_x and CO concentrations shall be acceptable for this documentation, provided a hot air probe or equivalent device is used to prevent error due to high stack temperature, and three sets of concentration measurements are made and averaged. Portable NO_x and CO analyzers shall also be acceptable for this documentation;

(iii) documentation within 60 days following initial engine start-up and biennially thereafter, for emissions of NO_x and CO, measured in accordance with United States Environmental Protection Agency (EPA) Reference Method 7E or 20 for NO_x and Method 10 for CO. Exhaust flow rate may be determined from measured fuel flow rate and EPA Method 19. California Air Resources Board Method A-100 (adopted June 29, 1983) is an acceptable alternate to EPA test methods. Modifications to these methods will be subject to the prior approval of the Source and Mobile Monitoring Division of the commission. Emissions shall be measured and recorded in the as-found operating condition; however, compliance determinations shall not be established during start-up, shutdown, or under breakdown conditions. An owner or operator may submit to the appropriate regional office a report of a valid emissions test performed in Texas, on the same engine, conducted no more than 12 months prior to the most recent start of construction date, in lieu of performing an emissions test within 60 days following engine start-up at the new site. Any such engine shall be sampled no less frequently than biennially (or every 15,000 hours of elapsed run time, as recorded by an elapsed run time meter) and upon request of the executive director. Following the initial compliance test, in lieu of performing stack sampling on a biennial calendar basis, an owner or operator may elect to install and operate an elapsed operating time meter and shall test the engine within 15,000 hours of engine operation after the previous emission test. The owner or operator who elects to test on an operating hour schedule shall submit in writing, to the appropriate regional office, biennially after initial sampling, documentation of the actual recorded hours of engine operation since the previous emission test, and an estimate of the date of the next required sampling.

(3) For any gas turbine rated 500 hp or more, subparagraphs (A) and (B) of this paragraph shall apply.

(A) The emissions of NO_x shall not exceed 3.0 g/hp-hr for gas-firing.

(B) The turbine shall meet all applicable NO_x and sulfur dioxide (SO_2) (or fuel sulfur) emissions limitations, monitoring requirements, and reporting requirements of EPA New Source Performance Standards Subpart GG--Standards of Performance for Stationary Gas Turbines. Turbine hp rating shall be based on turbine base load, fuel lower heating value, and International Standards Organization Standard Day Conditions of 59 degrees Fahrenheit, 1.0 atmosphere and 60% relative humidity.

(4) Any engine or turbine rated less than 500 hp or used for temporary replacement purposes shall be exempt from the emission limitations of paragraphs (2) and (3) of this section. Temporary replacement engines or turbines shall be limited to a maximum of 90 days of operation after which they shall be removed or rendered physically inoperable.

(5) Gas fuel shall be limited to: sweet natural gas or liquid petroleum gas, fuel gas containing no more than ten grains total sulfur per 100 dry standard cubic feet, or field gas. If field gas contains more than 1.5 grains hydrogen sulfide or 30 grains total sulfur compounds per 100 standard cubic feet (sour gas), the engine owner or operator shall maintain records, including at least quarterly measurements of fuel hydrogen sulfide and total sulfur content, which demonstrate that the annual SO_2 emissions from the facility do not exceed 25 tons per year (tpy). Liquid fuel shall be petroleum distillate oil that is not a blend containing waste oils or solvents and contains less than 0.3% by weight sulfur.

(6) There will be no violations of any National Ambient Air Quality Standard (NAAQS) in the area of the proposed facility. Compliance with this condition shall be demonstrated by one of the following three methods:

(A) ambient sampling or dispersion modeling accomplished pursuant to guidance obtained from the executive director. Unless otherwise documented by actual test data, the following nitrogen dioxide (NO_2)/ NO_x ratios shall be used for modeling NO_2 NAAQS;

	NO_x Emission Rate (Q)	
<u>Device</u>	<u>g/hp-hr</u>	<u>NO_2/NO_x Ratio</u>

IC Engine	Less than 2.0	0.4
IC Engine	2.0 thru 10.0	$0.15 + (0.5/Q)$
IC Engine	Greater than 10.0	0.2
Turbines	0.25	
IC Engine with catalytic converter		0.85

(B) all existing and proposed engine and turbine exhausts are released to the atmosphere at a height at least twice the height of any surrounding obstructions to wind flow. Buildings, open-sided roofs, tanks, separators, heaters, covers, and any other type of structure are considered as obstructions to wind flow if the distance from the nearest point on the obstruction to the nearest exhaust stack is less than five times the lesser of the height, Hb, and the width, Wb, where:

Hb = maximum height of the obstruction, and
Wb = projected width of obstruction =

$$2\sqrt{\frac{lw}{3.141}}$$

where:

L = length of obstruction
W = width of obstruction

(C) the total emissions of NO_x (nitrogen oxide plus NO₂) from all existing and proposed facilities on the property do not exceed the most restrictive of the following:

- (i) 250 tpy;
- (ii) the value (0.3125 D) tpy, where D equals the shortest distance in feet from any existing or proposed stack to the nearest property line.

(7) Upon issuance of a standard permit for electric generating units, registrations under this section for engines or turbines used to generate electricity will no longer be accepted, except for:

- (A) engines or turbines used to provide power for the operation of facilities registered under the Air Quality Standard Permit for Concrete Batch Plants;
- (B) engines or turbines satisfying the conditions for facilities permitted by rule under Subchapter E of this title (relating to Aggregate and Pavement); or
- (C) engines or turbines used exclusively to provide power to electric pumps used for irrigating crops.

Adopted May 23, 2001

Effective June 13, 2001

Reportable Emission Events
§101.201. Emissions Event Reporting and Recordkeeping Requirements

(a) The following requirements for reportable emissions events apply.

(1) As soon as practicable, but not later than 24 hours after the discovery of an emissions event, the owner or operator of a regulated entity shall:

- (A) determine if the event is a reportable emissions event; and
- (B) notify the commission office for the region in which the regulated entity is located, and all appropriate local air pollution control agencies with jurisdiction, if the emissions event is reportable.

(2) The initial 24-hour notification for reportable emissions events, with the exception of emissions from boilers or combustion turbines referenced in the definition of reportable quantity (RQ) in §101.1 of this title (relating to Definitions) for each regulated entity, must at a minimum, identify for each emissions point with emissions that exceed an RQ:

- (A) the name of the owner or operator of the regulated entity experiencing an emissions event;
- (B) the commission Regulated Entity Number of the regulated entity experiencing an emissions event, if a Regulated Entity Number exists, or if there is not a Regulated Entity Number, the air account number of the regulated entity. If a Regulated Entity Number and air account number do not exist, then identify the location of the release and a contact telephone number;
- (C) the common name of the process units or areas, the common name of the facilities that incurred the emissions event, and the common name of the emission points where the unauthorized emissions exceeded an RQ were released to the atmosphere;
- (D) the date and time of the discovery of the emissions;
- (E) the estimated duration of the emissions;
- (F) the compound descriptive type of the individually listed compounds or mixtures of air contaminants released during the emissions event, in the definition of RQ in §101.1 of this title that are known through common process knowledge, past engineering analysis, or testing to have equaled or exceeded the RQ;
- (G) the estimated total quantities for those compounds or mixtures described in subparagraph (F) of this paragraph;
- (H) the best known cause of the emissions event at the time of the initial 24-hour notification, if known; and
- (I) the actions taken, or being taken, to correct the emissions event and minimize the emissions.

(3) The initial 24-hour notification for reportable emissions events for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title must identify for each emission point with excess opacity that exceeds the RQ by more than 15%:

- (A) the name of the owner or operator of the regulated entity experiencing an emissions event;
- (B) the commission Regulated Entity Number of the regulated entity experiencing an emissions event, if a Regulated Entity Number exists, or if there is not a Regulated Entity Number, the air account number of the regulated entity. If a Regulated Entity Number and air account number do not exist, then identify the location of the release and a contact telephone number;
- (C) the best known cause of the emissions event, if known at the time of notification;
- (D) the common name of the process units or areas, the common name of the facilities that experienced the emissions event, and the common name of the emission points where the unauthorized opacity that exceeded the RQ occurred;
- (E) the date and time of the discovery of the emissions event;

- (F) the estimated duration or expected duration of the emissions;
- (G) the estimated opacity; and
- (H) the actions taken, or being taken, to correct the emissions event and minimize the emissions.

(4) The owner or operator of a regulated entity experiencing a reportable emissions event that also requires an initial notification under §327.3 of this title (relating to Notification Requirements) may satisfy the initial 24-hour notification requirements of this section by complying with the requirements under §327.3 of this title.

(b) The owner or operator of a regulated entity experiencing an emissions event shall create a final record of all reportable and non-reportable emissions events as soon as practicable, but no later than two weeks after the end of an emissions event. Final records must be maintained on-site for a minimum of five years and be made readily available upon request to commission staff or personnel of any air pollution program with jurisdiction. If a regulated entity is not normally staffed, records of emissions events may be maintained at the staffed location within Texas that is responsible for the day-to-day operations of the regulated entity.

(1) The final record of a reportable emissions event must identify for all emission points involved in the emissions event:

(A) the name of the owner or operator of the regulated entity experiencing an emissions event;

(B) the commission Regulated Entity Number of the regulated entity experiencing an emissions event, if a Regulated Entity Number and air account number exists, or if there is not a Regulated Entity Number, the air account number of the regulated entity. If a Regulated Entity Number and air account number do not exist, then identify the location of the release and a contact telephone number;

(C) the physical location of the points at which emissions to the atmosphere occurred;

(D) the common name of the process units or areas, the common name and the agency-established facility identification number of the facilities that experienced the emissions event, and the common name and the agency-established emission point numbers where the unauthorized emissions were released to the atmosphere. Owners or operators of those facilities and emission points that the agency has not established facility identification numbers or emission point numbers for are not required to provide the facility identification numbers and emission point numbers in the report, but are required to provide the common names in the report.

(E) the date and time of the discovery of the emissions event;

(F) the estimated duration of the emissions;

(G) the compound descriptive type of all individually listed compounds or mixtures of air contaminants in the definition of RQ in §101.1 of this title, from all emission points involved in the emissions event, that are known through common process knowledge or past engineering analysis or testing to have been released during the emissions event, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title. Compounds or mixtures of air contaminants, that have an RQ greater than or equal to 100 pounds and the amount released is less than ten pounds in a 24-hour period, are not required to be specifically listed in the report, instead these compounds or mixtures of air contaminants may be identified together as "other";

(H) the estimated total quantities for those compounds or mixtures described in subparagraph (G) of this paragraph; the preconstruction authorization number or rule citation of the standard permit, permit by rule, or rule, if any, governing the facilities involved in the emissions event; and the authorized emissions limits, if any, for the facilities involved in the emissions events, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title, which record only the authorized opacity limit and the estimated opacity during the emissions event. Good engineering practice and methods must be used to provide reasonably accurate representations for emissions and opacity. Estimated emissions from compounds or mixtures of air contaminants that are identified as "other" under subparagraph (G) of

this paragraph, are not required for each individual compound or mixture of air contaminants, however, a total estimate of emissions must be provided for the category identified as "other";

(I) the basis used for determining the quantity of air contaminants emitted, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title;

(J) the best known cause of the emissions event at the time of reporting;

(K) the actions taken, or being taken, to correct the emissions event and minimize the emissions;

and

(L) any additional information necessary to evaluate the emissions event.

(2) Records of non-reportable emissions events must identify:

(A) the name of the owner or operator of the regulated entity experiencing an emissions event;

(B) the commission Regulated Entity Number and air account number of the regulated entity experiencing an emissions event, if a Regulated Entity Number and air account number exists, or if there is not a Regulated Entity Number, the air account number of the regulated entity. If a Regulated Entity Number and air account number do not exist, then identify the location of the release and a contact telephone number;

(C) the physical location of the points at which emissions to the atmosphere occurred;

(D) the common name of the process units or areas, the common name and the agency-established facility identification number of the facilities that experienced the emissions event, and the common name and the agency-established emission point numbers where the unauthorized emissions were released to the atmosphere. Owners or operators of those facilities and emission points that the commission has not established facility identification numbers or emission point numbers for are not required to provide the facility identification numbers and emission point numbers in the report, but are required to provide the common names in the report;

(E) the date and time of the discovery of the emissions event;

(F) the estimated duration of the emissions;

(G) the compound descriptive type of the individually listed compounds or mixtures of air contaminants, in the definition of RQ in §101.1 of this title, from all emission points involved in the emissions event, that are known through common process knowledge or past engineering analysis, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title and that were unauthorized. Compounds or mixtures of air contaminants, that have an RQ greater than or equal to 100 pounds and the amount released is less than ten pounds in a 24-hour period, are not required to be specifically listed in the report, instead these compounds or mixtures of air contaminants may be identified together as "other";

(H) the estimated total quantities and the authorized emissions limits for those compounds or mixtures described in subparagraph (G) of this paragraph; the preconstruction authorization number or rule citation of the standard permit, permit by rule, or rule, if any, governing the facilities involved in the emissions event; and the authorized emissions limits, if any, for the facilities involved in the emissions events, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title, which record only the authorized opacity limit and the estimated opacity during the emissions event. Good engineering practice and methods must be used to provide reasonably accurate representations for emissions and opacity. Estimated emissions from compounds or mixtures of air contaminants that are identified as "other" under subparagraph (G) of this paragraph, are not required for each individual compound or mixture of air contaminants, however, a total estimate of emissions must be provided for the category identified as "other";

(I) the basis used for determining the quantity of air contaminants emitted, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title;

(J) the best known cause of the emissions event at the time of recording;

(K) the actions taken, or being taken, to correct the emissions event and minimize the emissions;

and

(L) any additional information necessary to evaluate the emissions event.

(c) For all reportable emissions events, if the information required in subsection (b) of this section differs from the information provided in the initial 24-hour notification under subsection (a) of this section, the owner or operator of the regulated entity shall submit a copy of the final record to the commission office for the region in which the regulated entity is located and to appropriate local air pollution agencies with jurisdiction no later than two weeks after the end of the emissions event. If the owner or operator does not submit a record under this subsection, the information provided in the initial 24-hour notification under subsection (a) of this section will be the final record of the emissions event, provided the initial 24-hour notification was submitted electronically in accordance with subsection (g) of this section.

(d) The owner or operator of a boiler or combustion turbine, as defined in §101.1 of this title, fueled by natural gas, coal, lignite, wood, or fuel oil containing hazardous air pollutants at a concentration of less than 0.02% by weight, that is equipped with a continuous emission monitoring system that completes a minimum of one operating cycle (sampling, analyzing, and data recording) for each successive 15-minute interval, and is required to submit excess emission reports by other state or federal requirements, is exempt from creating, maintaining, and submitting final records of reportable and non-reportable emissions events of the boiler or combustion turbine under subsections (b) and (c) of this section if the notice submitted under subsection (a) of this section contains the information required under subsection (b) of this section.

(e) As soon as practicable, but not later than 24 hours after the discovery of an excess opacity event, as defined in §101.1 of this title, where the owner or operator was not already required to provide an initial 24-hour notification under subsection (a)(2) or (3) of this section, the owner or operator shall notify the commission office for the region in which the regulated entity is located, and all appropriate local air pollution control agencies with jurisdiction. In the notification, the owner or operator shall identify:

- (1) the name of the owner or operator of the regulated entity experiencing the excess opacity event;
- (2) the commission Regulated Entity Number and air account number of the regulated entity experiencing an opacity event, if a Regulated Entity Number and air account number exists, or if there is not a Regulated Entity Number, the air account number of the regulated entity. If a Regulated Entity Number and air account number do not exist, then identify the location of the release and a contact telephone number;
- (3) the physical location of the excess opacity event;
- (4) the common name of the process units or areas, the common name of the facilities where the excess opacity event occurred, and the common name of the emission points where the excess opacity event occurred;
- (5) the date and time of the discovery of the excess opacity event;
- (6) the estimated duration of the excess opacity;
- (7) the estimated opacity;
- (8) the authorized opacity limit for the facilities having the excess opacity event;
- (9) the best known cause of the excess opacity event at the time of the notification; and
- (10) the actions taken, or being taken, to correct the excess opacity event.

(f) The owner or operator of any regulated entity subject to the provisions of this section shall perform, upon request by the executive director or any air pollution control agency with jurisdiction, a technical evaluation of each emissions event. The evaluation must include at least an analysis of the probable causes of each emissions event and any necessary actions to prevent or minimize recurrence. The evaluation must be submitted in writing to the executive director and to the appropriate local air pollution agencies with jurisdiction within 60 days from the date of request. The 60-day period may be extended by the executive director. Additionally, the owner or operator of a regulated entity experiencing an emissions event must provide, in writing, additional or more detailed information regarding the emissions event when requested

by the executive director or any air pollution control agency with jurisdiction, within the time established in the request.

(g) On and after January 1, 2003, notifications and reports required in subsection (c) of this section must be submitted electronically to the commission using the electronic forms provided by the commission. On and after January 1, 2004, notifications required in subsections (a) and (c) of this section must be submitted via commission's secure Web server, facsimile, or electronic mail to the commission using electronic forms provided by the commission. Notwithstanding the requirement to report initial 24-hour notifications electronically after January 1, 2004, the owner or operator of a regulated entity experiencing a reportable emissions event that also requires an initial notification under §327.3 of this title, is not required to report the event electronically under this subsection provided the owner or operator complies with the requirements under §327.3 of this title and in subsections (a) and (c) of this section. If the initial notification is not submitted by using an online form on the commission's secure Web server, the owner or operator must submit the identical information on the commission's secure Web server within 48 hours of discovery of the event. In the event the commission's server is unavailable due to technical failures or scheduled maintenance, events may be reported via facsimile to the appropriate regional office. The commission will provide an alternative means of notification in the event that the commission's electronic reporting system is inoperative. Electronic notification and reporting is not required for small businesses that meet the small business definition in Texas Water Code, §5.135(g)(2) and to appropriate local air pollution control agencies with jurisdiction. Small businesses shall provide notifications and reporting by any viable means that meet the time frames required by this section.

(h) Annual emissions event reporting: beginning in calendar year 2007, on or before March 31 of each calendar year or as directed by the executive director, each owner or operator of a regulated entity, as defined in §101.1 of this title that is subject to reporting under §101.10 of this title (relating to Emissions Inventory Requirements), and those that are not subject to reporting under §101.10 of this title, but are located in nonattainment, maintenance, early action compact areas, Nueces County, and San Patricio County, that experienced at least one emissions event during the calendar year shall report to the executive director, and all appropriate local air pollution control agencies with jurisdiction, the following:

(1) the total number of reportable and the total number of non-reportable emissions events experienced at the regulated entity;

(2) the estimated total quantities for all compounds or mixtures of air contaminants, by compound or mixture, in the definition of RQ in §101.1 of this title that, by facility, were emitted during emissions events at the regulated entity. Compounds or mixtures of air contaminants, that have an RQ greater than or equal to 100 pounds and the amount released is less than one pound in a 24-hour period, are not required to be included in the report. Good engineering practice and methods must be used to provide reasonably accurate representations for emissions and opacity. This paragraph does not apply to boilers and combustion turbines referenced in the definition of RQ in §101.1 of this title that must report only the estimated opacities during emissions events and duration of unauthorized opacity; and

(3) owners and operators of regulated entities that are not subject to reporting under §101.10 of this title must provide annual emissions event reporting electronically by using an online form on the commission's secure Web server. The commission will provide an alternative means of reporting in the event that the commission's electronic reporting system is inoperative. If the commission's server is unavailable due to technical failures or scheduled maintenance, the annual reports may be provided through alternative means to the executive director. Annual electronic reporting is not required for small businesses that meet the small business definition in Texas Water Code, §5.135(g)(2) and to appropriate local air pollution control agencies with jurisdiction. Small businesses shall provide annual reporting by any viable means that meet the time frames required by this section.

(4) owners and operators of regulated entities that are subject to reporting under §101.10 of this title must provide the information required by this subsection as part of their reporting under §101.10 of this

title.

Adopted December 14, 2005

Effective January 5, 2006

Reportable Quantity (RQ) Defined

(88) Reportable emissions event--Any emissions event that in any 24-hour period, results in an unauthorized emission from any emissions point equal to or in excess of the reportable quantity as defined in this section.

(89) Reportable quantity (RQ)--Is as follows:

(A) for individual air contaminant compounds and specifically listed mixtures by name or Chemical Abstracts Service (CAS) number, either:

(i) the lowest of the quantities:

(I) listed in 40 Code of Federal Regulations (CFR) Part 302 , Table 302.4, the column "final RQ";

(II) listed in 40 CFR Part 355, Appendix A, the column "Reportable Quantity"; or

(III) listed as follows:

(-a-) acetaldehyde - 1,000 pounds, except in the Houston-Galveston-Brazoria (HGB) and Beaumont-Port Arthur (BPA) ozone nonattainment areas as defined in paragraph (71)(E)(i) and (iii) of this section, where the RQ must be 100 pounds;

(-b-) butanes (any isomer) - 5,000 pounds;

(-c-) butenes (any isomer, except 1,3-butadiene) - 5,000 pounds, except in the HGB and BPA ozone nonattainment areas as defined in paragraph (71)(E)(i) and (iii) of this section, where the RQ must be 100 pounds;

(-d-) carbon monoxide - 5,000 pounds;

(-e-) 1-chloro-1,1-difluoroethane (HCFC-142b) - 5,000 pounds;

(-f-) chlorodifluoromethane (HCFC-22) - 5,000 pounds;

(-g-) 1-chloro-1-fluoroethane (HCFC-151a) - 5,000 pounds;

(-h-) chlorofluoromethane (HCFC-31) - 5,000 pounds;

(-i-) chloropentafluoroethane (CFC-115) - 5,000 pounds;

(-j-) 2-chloro-1,1,1,2-tetrafluoroethane (HCFC-124) - 5,000 pounds;

(-k-) 1-chloro-1,1,2,2 tetrafluoroethane (HCFC-124a) - 5,000 pounds;

(-l-) 1,1,1,2,3,4,4,5,5,5-decafluoropentane (HFC 43-10mee) - 5,000 pounds;

(-m-) decanes (any isomer) - 5,000 pounds;

(-n-) 1,1-dichloro-1-fluoroethane (HCFC-141b) - 5,000 pounds;

(-o-) 3,3-dichloro-1,1,2,2-pentafluoropropane (HCFC-225ca) - 5,000 pounds;

(-p-) 1,3-dichloro-1,1,2,2,3-pentafluoropropane (HCFC-225cb) - 5,000 pounds;

(-q-) 1,2-dichloro-1,1,2,2-tetrafluoroethane (CFR-114) - 5,000 pounds;

(-r-) 1,1,-dichlorotetrafluoroethane (CFC-114a) - 5,000 pounds;

(-s-) 1,2-dichloro-1,1,2-trifluoroethane (HCFC-123a) - 5,000 pounds;

(-t-) 1,1-difluoroethane (HFC-152a) - 5,000 pounds;

(-u-) difluoromethane (HFC-32) - 5,000 pounds;

(-v-) ethanol - 5,000 pounds;

(-w-) ethylene - 5,000 pounds, except in the HGB and BPA ozone nonattainment areas as defined in paragraph (71)(E)(i) and (iii) of this section, where the RQ must be 100 pounds;

(-x-) ethylfluoride (HFC-161) - 5,000 pounds;

(-y-) 1,1,1,2,3,3,3-heptafluoropropane (HFC-227ea);

(-z-) 1,1,1,3,3,3-hexafluoropropane (HFC-236fa) - 5,000 pounds;

(-aa-) 1,1,1,2,3,3-hexafluoropropane (HFC-236ea) - 5,000 pounds;

(-bb-) hexanes (any isomer) - 5,000 pounds;
(-cc-) isopropyl alcohol - 5,000 pounds;
(-dd-) mineral spirits - 5,000 pounds;
(-ee-) octanes (any isomer) - 5,000 pounds;
(-ff-) oxides of nitrogen - 200 pounds in ozone nonattainment, ozone maintenance, early action compact areas, Nueces County, and San Patricio County, and 5,000 pounds in all other areas of the state, which should be used instead of the RQs for nitrogen oxide and nitrogen dioxide provided in 40 CFR Part 302, Table 302.4, the column "final RQ";

(-gg-) pentachlorofluoroethane (CFR-111) - 5,000 pounds;
(-hh-) 1,1,1,3,3-pentafluorobutane (HFC-365mfc) - 5,000 pounds;
(-ii-) pentafluoroethane (HFC-125) - 5,000 pounds;
(-jj-) 1,1,2,2,3-pentafluoropropane (HFC-245ca) - 5,000 pounds;
(-kk-) 1,1,2,3,3-pentafluoropropane (HFC-245ea) - 5,000 pounds;
(-ll-) 1,1,1,2,3-pentafluoropropane (HFC-245eb) - 5,000 pounds;
(-mm-) 1,1,1,3,3-pentafluoropropane (HFC-245fa) - 5,000 pounds;
(-nn-) pentanes (any isomer) - 5,000 pounds;
(-oo-) propane - 5,000 pounds;
(-pp-) propylene - 5,000 pounds, except in the HGB and BPA ozone nonattainment areas as defined in paragraph (71)(E)(i) and (iii) of this section, where the RQ must be 100 pounds;
(-qq-) 1, 1, 2, 2-tetrachlorodifluoroethane (CFR -112) - 5,000 pounds;
(-rr-) 1,1,1,2-tetrachlorodifluoroethane (CFC-112a) - 5,000 pounds;
(-ss-) 1,1,2,2-tetrafluoroethane (HFC-134) - 5,000 pounds;
(-tt-) 1,1,1,2-tetrafluoroethane (HFC-134a) - 5,000 pounds;
(-uu-) 1,1,2-trichloro-1,2,2-trifluoroethane (CFR-113) - 5,000 pounds;
(-vv-) 1,1,1-trichloro-2,2,2-trifluoroethane (CFC-113a) - 5,000 pounds;
(-ww-) 1,1,1-trifluoro-2,2-dichloroethane (HCFC-123) - 5,000 pounds;
(-xx-) 1,1,1-trifluoroethane (HFC-143a) - 5,000 pounds;
(-yy-) trifluoromethane (HFC-23) - 5,000 pounds; or
(-zz-) toluene - 1,000 pounds, except in the HGB and BPA ozone nonattainment areas as defined in paragraph (71)(E)(i) and (iii) of this section, where the RQ must be 100 pounds;

(ii) if not listed in clause (i) of this subparagraph, 100 pounds;

(B) for mixtures of air contaminant compounds:

(i) where the relative amount of individual air contaminant compounds is known through common process knowledge or prior engineering analysis or testing, any amount of an individual air contaminant compound that equals or exceeds the amount specified in subparagraph (A) of this paragraph;

(ii) where the relative amount of individual air contaminant compounds in subparagraph (A)(i) of this paragraph is not known, any amount of the mixture that equals or exceeds the amount for any single air contaminant compound that is present in the mixture and listed in subparagraph (A)(i) of this paragraph;

(iii) where each of the individual air contaminant compounds listed in subparagraph (A)(I) of this paragraph are known to be less than 0.02% by weight of the mixture, and each of the other individual air contaminant compounds covered by subparagraph (A)(ii) of this paragraph are known to be less than 2.0% by weight of the mixture, any total amount of the mixture of air contaminant compounds greater than or equal to 5,000 pounds; or

(iv) where natural gas excluding carbon dioxide, water, nitrogen, methane, ethane, noble gases, hydrogen, and oxygen or air emissions from crude oil are known to be in an amount greater than or equal to 5,000 pounds or the associated hydrogen sulfide and mercaptans in a total amount greater than 100 pounds, whichever occurs first;

(C) for opacity from boilers and combustion turbines as defined in this section fueled by natural gas, coal, lignite, wood, fuel oil containing hazardous air pollutants at a concentration of less than 0.02% by weight, opacity that is equal to or exceeds 15 additional percentage points above the applicable limit, averaged over a six-minute period. Opacity is the only RQ applicable to boilers and combustion turbines described in this paragraph; or

(D) for facilities where air contaminant compounds are measured directly by a continuous emission monitoring system providing updated readings at a minimum 15-minute interval an amount, approved by the executive director based on any relevant conditions and a screening model, that would be reported prior to ground level concentrations reaching at any distance beyond the closest regulated entity property line:

- (i) less than one-half of any applicable ambient air standards; and
- (ii) less than two times the concentration of applicable air emission limitations.

Maintenance, Startup, and Shutdown Activities

§101.211. Scheduled Maintenance, Startup and Shutdown Reporting and Recordkeeping Requirements.

(a) The owner or operator of a regulated entity conducting a scheduled maintenance, startup, or shutdown activity shall notify the commission office for the region in which the regulated entity is located and all appropriate local air pollution control agencies with jurisdiction at least ten days prior to any scheduled maintenance, startup, or shutdown activity that is expected to cause an unauthorized emission that equals or exceeds the reportable quantity (RQ) as defined in §101.1 of this title (relating to Definitions), by emissions point in any 24-hour period and/or an activity where the owner or operator expects only an excess opacity event as defined in §101.1 of this title. If notice cannot be given ten days prior to a scheduled maintenance, startup, or shutdown activity, notification must be given as soon as practicable prior to the scheduled activity. Maintenance, startup, or shutdown activities where the actual emissions exceed the emissions in the notification by more than an RQ or for which a notification was not submitted prior to the activity are either upsets or unplanned maintenance, startup, or shutdown activities, depending upon the reason for exceeding the estimate. Excess opacity events where unauthorized emissions result are emissions events. Owners and operators of a regulated entity with emissions events shall report such events as emissions events in accordance with the requirements in §101.201 of this title, or this section as applicable and §101.222 of this title (relating to Demonstrations).

(1) The notification for a scheduled maintenance, startup, or shutdown activity, except for boilers and combustion turbines referenced in the definition of RQ in §101.1 of this title, must identify:

- (A) the name of the owner or operator;
- (B) the commission Regulated Entity Number of the regulated entity, if a Regulated Entity Number and air account number exist(s), or if there is not a Regulated Entity Number, the air number of the regulated entity. If a Regulated Entity Number and air account number do not exist, then identify the location of the release and a contact telephone number;
- (C) the physical location of the points at which emissions from the scheduled maintenance, startup, or shutdown activity will occur;
- (D) the type of scheduled maintenance, startup, or shutdown activity and the reason for the scheduled activity;
- (E) the expected date and time of the scheduled maintenance, startup, or shutdown activity, and expected duration of any maintenance activity;
- (F) the common name of the process units or areas, the common name and the agency-established facility identification number of the facilities that will be involved in the emissions activity, and the common name and the agency-established emission point numbers where the unauthorized emissions may be released to the atmosphere. Owners or operators of those facilities and emission points that the agency has not established facility identification numbers or emission point numbers for are not required to provide the facility identification numbers and emission point numbers in the report, but are required to provide the common names in the report;
- (G) the expected duration of the emissions from the scheduled maintenance, startup, or shutdown activity;
- (H) the compound descriptive type of the individually listed compounds or mixtures of air contaminants, in the definition of RQ in §101.1 of this title, for all emission points involved in the emissions activity, that through common process knowledge or past engineering analysis or testing are expected to equal or exceed the RQ. Compounds or mixtures of air contaminants, that have an RQ greater than or equal to 100 pounds and the amount released is less than ten pounds in a 24-hour period, are not required to be specifically listed in the report, instead these compounds or mixtures of air contaminants may be identified together as "other";
- (I) the estimated total quantities for those compounds or mixtures described in subparagraph (H)

of this paragraph; the preconstruction authorization number or rule citation of the standard permit, permit by rule, or rule, if any, governing the facilities involved in the activity; authorized emissions limits, if any, for the facilities involved in the emissions activity, and, if applicable, the estimated opacity and the authorized opacity limit. Good engineering practice and methods must be used to provide reasonably accurate representations for emissions and opacity. Estimated emissions from compounds or mixtures of air contaminants that are identified as "other" under subparagraph (H) of this paragraph, are not required for each individual compound or mixture of air contaminants, however, a total estimate of emissions must be provided for the category identified as "other";

(J) the basis used for determining the quantity of air contaminants to be emitted; and

(K) the actions taken to minimize the emissions from the scheduled maintenance, startup, or shutdown activity.

(2) The notification for a scheduled maintenance, startup, or shutdown activity involving a boiler or combustion turbine referenced in the definition of RQ in §101.1 of this title, or where the owner or operator expects only an excess opacity event and the owner or operator was not already required to provide a notification under paragraph (1) of this subsection, must identify:

(A) the name of the owner or operator;

(B) the commission Regulated Entity Number of the regulated entity, if a Regulated Entity Number and air account number exist(s), or if there is not a Regulated Entity Number, the air account number of the regulated entity. If a Regulated Entity Number and air account number do not exist, then identify the location of the release and a contact telephone number;

(C) the physical location of the scheduled maintenance, startup, or shutdown activity;

(D) the type of scheduled maintenance, startup, or shutdown activity and the reason for the scheduled activity;

(E) the common name of the process units or areas, the common name and the agency-established facility identification numbers of the facility that experienced the excess opacity event, and the common name and the agency-established emission point numbers where the excess opacity event occurred. Owners or operators of those facilities and emission points that the agency has not established facility identification numbers or emission point numbers for are not required to provide the facility identification numbers and emission point numbers in the report, but are required to provide the common names in the report;

(F) the expected date and time of the scheduled maintenance, startup, or shutdown activity, and expected duration of any maintenance activity;

(G) the estimated duration of the emissions from the scheduled maintenance, startup, or shutdown activity;

(H) the estimated opacity and the authorized opacity limit for those emission points that unauthorized opacity is expected; and

(I) the actions taken, or being taken, to minimize the emissions from the scheduled maintenance, startup, or shutdown activity.

(b) The owner or operator of a regulated entity conducting a scheduled maintenance, startup, or shutdown activity shall create a final record of all scheduled maintenance, startup, and shutdown activities with unauthorized emissions, or with opacity exceedances from boilers and combustion turbines referenced in the definition of RQ in §101.1 of this title. The final record must be created as soon as practicable, but no later than two weeks after the end of each scheduled activity. Final records must be maintained on-site for a minimum of five years and be made readily available upon request to commission staff or personnel of any air pollution program with jurisdiction. If a regulated entity is not normally staffed, records of scheduled maintenance, startup, and shutdown activities may be maintained at the staffed location within Texas that is responsible for day-to-day operations of the regulated entity. Such scheduled activity records must identify:

(1) for owners and operators of regulated entities that were required to notify under subsection (a) of this section:

- (A) the name of the owner or operator;
- (B) the commission Regulated Entity Number of the regulated entity, if a Regulated Entity Number and air account number exist(s), or if there is not a Regulated Entity Number, the air account number of the regulated entity. If a Regulated Entity Number and air account number do not exist, then identify the location of the regulated entity and a contact telephone number;
- (C) the physical location of the scheduled points at which emissions from the maintenance, startup, or shutdown activity occurred;
- (D) the type of scheduled maintenance, startup, or shutdown activity and the reason for the scheduled activity;
- (E) the common name of the process units or areas, the common name and the agency-established facility identification number of the facilities that experienced the emissions activity, and the common name and the agency-established emission point numbers where the unauthorized emissions were released to the atmosphere. Owners or operators of those facilities and emission points that the agency has not established facility identification numbers or emission point numbers for are not required to provide the facility identification numbers and emission point numbers in the report, but are required to provide the common names in the report;
- (F) the date and time of the scheduled maintenance, startup, or shutdown activity, and the duration of any maintenance activity;
- (G) the duration of the emissions from the scheduled maintenance, startup, or shutdown activity;
- (H) the compound descriptive type of all individually listed compounds or mixtures of air contaminants, in the definition of RQ in §101.1 of this title, involved in the emissions activity, that are known through common process knowledge or past engineering analysis or testing to have been released during the scheduled maintenance, startup, or shutdown activity, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title. Compounds or mixtures of air contaminants, that have an RQ greater than or equal to 100 pounds and the amount released is less than ten pounds in a 24-hour period, are not required to be specifically listed in the report instead these compounds or mixtures of air contaminants may be identified together as "other";
- (I) the estimated total quantities and the authorized emissions limits for those compounds or mixtures described in subparagraph (H) of this paragraph; the preconstruction authorization number or rule citation of the standard permit, permit by rule, or rule, any, governing the facilities involved in the scheduled maintenance, startup, or shutdown activity; authorized emissions limits, if any, for the facility involved in the scheduled maintenance, startup, or shutdown activity, and, if applicable, the estimated opacity and authorized opacity limit, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title that record only the authorized opacity limit and the estimated opacity during the emissions event. Good engineering practice and methods must be used to provide reasonably accurate representations for emissions and opacity. Estimated emissions from compounds or mixtures of air contaminants that are identified as "other" under subparagraph (H) of this paragraph are not required for each individual compound or mixture of air contaminants; however, a total estimate of emissions must be provided for the category identified as "other";
- (J) the basis used for determining the quantity of air contaminants to be emitted, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title; and
- (K) the actions taken to minimize the emissions from the scheduled maintenance, startup, or shutdown activity.

(2) for owners and operators of regulated entities that were not required to notify under subsection (a) of this section:

- (A) the name of the owner or operator;

(B) the commission Regulated Entity Number of the regulated entity if a Regulated Entity Number and air account number exist(s), or if there is not a Regulated Entity Number, the air account number of the regulated entity. If a Regulated Entity Number and air account number do not exist, then identify the location of the release and a contact telephone number;

(C) the physical location of the scheduled points at which emissions from the maintenance, startup, or shutdown activity occurred;

(D) the type of scheduled maintenance, startup, or shutdown activity and the reason for the scheduled activity;

(E) the common name of the process unit or areas, the common name and the agency-established facility identification numbers of the facilities that experienced the emissions activity, and the common name and the agency-established emission point numbers where the unauthorized emissions were released to the atmosphere. Owners or operators of those facilities and emission points that the agency has not established facility identification numbers or emission point numbers for are not required to provide the facility identification numbers and emission point numbers in the report, but are required to provide the common names in the report;

(F) the date and time of the scheduled maintenance, startup, or shutdown activity, and the duration of any maintenance activity;

(G) the duration of the emissions from the scheduled maintenance, startup, or shutdown activity;

(H) the compound descriptive type of the individually listed compounds or mixtures of air contaminants, in the definition of RQ in §101.1 of this title, that are known through common process knowledge, past engineering analysis, except for boilers or combustion turbines referenced in the definition of RQ in §101.1 of this title and that were unauthorized. Compounds or mixtures of air contaminants, that have an RQ greater than or equal to 100 pounds and the amount released is less than ten pounds in a 24-hour period, are not required to be specifically listed in the record instead these compounds or mixtures of air contaminants may be identified together as "other"; and

(I) the estimated total quantities and the authorized emissions limits for those compounds or mixtures described in subparagraph (H) of this paragraph. Good engineering practice and methods must be used to provide reasonably accurate representations for emissions and opacity. Estimated emissions from compounds or mixtures of air contaminants that are identified as "other" under subparagraph (H) of this paragraph are not required for each individual compound or mixture of air contaminants, however, a total estimate of emissions must be provided for the category identified as "other."

(c) For any scheduled maintenance, startup, or shutdown activity for which an initial notification was submitted under subsection (a) of this section, which does not provide all the information required in subsection (b) of this section or if the information has changed from the prior notification, the owner or operator of the regulated entity shall submit a final record as required by subsection (b) of this section to the commission office for the region in which the regulated entity is located and to appropriate local air pollution agencies with jurisdiction no later than two weeks after the end of the scheduled activity. If the owner or operator does not submit a record under this subsection, the information provided under subsection (a) of this section will be the final record of the scheduled activity.

(d) The owner or operator of a boiler or combustion turbine as defined in §101.1 of this title fueled by natural gas, coal, lignite, wood, or fuel oil containing hazardous air pollutants at a concentration of less than 0.02% by weight, that is equipped with a continuous emission monitoring system that completes a minimum of one operating cycle (sampling, analyzing, and data recording) for each successive 15-minute interval, and is required to submit excess emissions reports by other state or federal rules, is exempt from creating, maintaining, and submitting final records of scheduled maintenance, startup, and shutdown activities with unauthorized emissions under subsections (b) and (c) of this section, if the notice submitted under subsection (a) of this section contains the information required under subsection (b) of this section.

(e) The executive director may specify the amount, time, and duration of emissions that will be allowed

during the scheduled maintenance, startup, or shutdown activity. The owner or operator of any source subject to the provisions of this section shall submit a technical plan for any scheduled maintenance, startup, or shutdown activity when requested by the executive director with a copy to the appropriate local air pollution agencies with jurisdiction. The plan must contain a detailed explanation of the means by which emissions will be minimized during the scheduled maintenance, startup, or shutdown activity. For those emissions that must be released into the atmosphere, the plan must include the reasons such emissions cannot be reduced further.

(f) For annual scheduled maintenance, startup, and shutdown activity reporting on or before March 31 of each calendar year beginning in calendar year 2007, or as directed by the executive director, each owner or operator of a regulated entity site, as defined in §101.1 of this title that is subject to reporting under §101.10 of this title (relating to Emissions Inventory Reporting), and those that are not subject to reporting under §101.10 of this title but are located in nonattainment, maintenance, early action compact areas, Nueces County, and San Patricio County, that experienced at least one scheduled maintenance, startup, and shutdown activity during the calendar year must report to the executive director, and all appropriate local air pollution control agencies with jurisdiction:

(1) the number of reportable and non-reportable scheduled maintenance, startup, and shutdown activities experienced at the regulated entity; and

(2) the estimated total quantities for all compounds or mixtures, by compound or mixture, of air contaminants, in the definition of RQ in §101.1 of this title that, by facility, emitted during scheduled maintenance, startup, and shutdown activities at the regulated entity. Compounds or mixtures of air contaminants, that have an RQ greater than or equal to 100 pounds and the amount released is less than one pound in a 24-hour period, are not required to be included in the report. Good engineering practice and methods must be used to provide reasonably accurate representations for emissions and opacity. This paragraph does not apply to boilers and combustion turbines referenced in the definition of RQ in §101.1 of this title, that must report only the estimated opacities during emissions events and duration of unauthorized opacity; and

(3) owners and operators of regulated entities that are not subject to reporting under §101.10 of this title must report annual total emissions resulting from all scheduled maintenance, startup, and shutdown activities electronically by using an online form on the commission's secure Web server. The commission will provide an alternative means of reporting in the event that the commission's electronic reporting system is inoperative. If the commission's server is unavailable due to technical failures or scheduled maintenance, the annual reports may be reported to the executive director. Annual electronic reporting is not required for small businesses that meet the small business definition in Texas Water Code, §5.135(g)(2) and to appropriate local air pollution control agencies with jurisdiction. Small businesses shall provide annual reporting by any viable means that meet the time frames required by this section; and

(4) owners and operators of regulated entities that are subject to reporting under §101.10 of this title must provide the information required by this subsection as part of their reporting under §101.10 of this title.

Adopted December 14, 2005

Effective January 5, 2006

Emission Calculations

POINT SOURCE I.D. NUMBER: 12-21-GR-BS

EMISSION SOURCE DESCRIPTION: 500 MMBTU/Hr Glycol Regenerator-Burner Stack

DATA:

Emission Source:	<i>External Combustion Burner</i>
Annual Hours of Operation:	8760
Maximum Burner Rating (MMBTU/Hr):	0.500
Fuel Gas Heat of Combustion (BTU/scf):	1228
<i>(based on a representative wet gas analysis)</i>	
Sulfur Concentration of Fuel Gas (ppmv):	4
<i>(provided by operator)</i>	
Fuel Source:	<i>Natural Gas</i>

Max. Hourly Fuel Consumption (SCFH): = burner rating/fuel gas heat of combustion/80% efficiency = **508.96**

Max. Annual Fuel Consumption (MSCF/Yr): = hourly fuel consumption x annual hours = **4,458.49**

EMISSION FACTORS:

Unless otherwise noted, emission factors taken from EPA Publication AP-42, "Compilation of Air Pollution Emission Factors" - Natural Gas Combustion (Small Boilers). SO₂ emission factor based on 100% conversion of sulfur compounds in fuel gas, using H₂S fuel composition noted above.

EMISSION CALCULATIONS:

POLLUTANT:	EMISSION FACTOR (LBS/10 ⁶ SCF)	CALCULATED EMISSION RATES:	
		Hourly (lb/hr)	Annual (TPY)
Particulate Matter (filterable + condensable)	7.6	0.0039	0.0169
Sulfur Dioxide	0.675	0.0003	0.0015
Nitrogen Oxides	100	0.0509	0.2229
Carbon Monoxide	84	0.0428	0.1873
Methane (excluded from VOC total)	2.3	0.0012	0.0051
VOC	5.5	0.0028	0.0123
TOC	11	0.0056	0.0245
2-Methylnaphthalene (TAP)	0.0000240	0.0000	0.0000
3-Methylchloranthrene (TAP)	0.0000018	0.0000	0.0000
7,12-Dimethylbenz(a)anthracene (TAP)	0.0000160	0.0000	0.0000
Acenaphthene (TAP)	0.0000018	0.0000	0.0000
Acenaphthylene (TAP)	0.0000018	0.0000	0.0000
Anthracene (TAP)	0.0000024	0.0000	0.0000
Benz(a)anthracene (TAP)	0.0000018	0.0000	0.0000
Benzene (TAP)	0.0021000	0.0000	0.0000

POLLUTANT:	EMISSION FACTOR (LBS/10 ⁶ SCF)	CALCULATED EMISSION RATES:	
		Hourly (lb/hr)	Annual (TPY)
Benzo(a)pyrene (TAP)	0.0000012	0.0000	0.0000
Benzo(b)fluoranthene (TAP)	0.0000018	0.0000	0.0000
Benzo(g,h,i)perylene (TAP)	0.0000012	0.0000	0.0000
Benzo(k)fluoranthene (TAP)	0.0000018	0.0000	0.0000
Chrysene (TAP)	0.0000018	0.0000	0.0000
Dibenzo(a,h)anthracene (TAP)	0.0000012	0.0000	0.0000
Dichlorobenzene (TAP)	0.0012000	0.0000	0.0000
Fluorathene (TAP)	0.0000030	0.0000	0.0000
Fluorene (TAP)	0.0000028	0.0000	0.0000
Formaldehyde (TAP)	0.0750000	0.0000	0.0002
Hexane (TAP)	1.8000000	0.0009	0.0040
Indeno(1,2,3-cd)pyrene (TAP)	0.0000018	0.0000	0.0000
Naphthalene (TAP)	0.0006100	0.0000	0.0000
Phenanthrene (TAP)	0.0000170	0.0000	0.0000
Pyrene (TAP)	0.0000050	0.0000	0.0000
Toluene (TAP)	0.0034000	0.0000	0.0000
Arsenic (TAP)	0.0002000	0.0000	0.0000
Beryllium (TAP)	0.0000120	0.0000	0.0000
Cadmium (TAP)	0.0011000	0.0000	0.0000
Chromium (TAP)	0.0014000	0.0000	0.0000
Cobalt (TAP)	0.0000840	0.0000	0.0000
Manganese (TAP)	0.0003800	0.0000	0.0000
Mercury (TAP)	0.0002600	0.0000	0.0000
Nickel (TAP)	0.0021000	0.0000	0.0000
Selenium (TAP)	0.0000240	0.0000	0.0000
Total TAPs		0.00	0.00
Total VOC-TAPs		0.00	0.00
Total Non VOC & Non TAP-HC		0.00	0.01
Total VOC		0.00	0.01

Emission Calculations

POINT SOURCE I.D. NUMBER:

13-21-GR-SC

EMISSION SOURCE DESCRIPTION:

Glycol Regenerator-Still Column

Data:

Emission Source:	Glycol Regenerator Still Column Vapors
Annual Hours of Operation:	8760
Absorber Temperature (°F):	85
Absorber Pressure (psig):	500
Wet Gas Water Content:	Saturated (conservative estimate)
Wet Gas Speciation:	Representative Wet Gas Analysis; refer to Southcross Energy Report No.:24-7077-24 in Appendix C
Maximum Dry Gas Flowrate (MMSCFD):	1.5
Maximum Dry Gas Water Content:	7.0 lbs/MMSCF
Lean Glycol Water Content:	1.5% (program default)
Maximum Lean Glycol Circulation Rate (Gal/lb H2O):	3
Glycol Pump Fuel Rate (SCF/Gal of Glycol):	2.8
Glycol Pump Flash Separator (GPFS):	110°F @ 80-psig; 100% recycle/recompression control
Stripping Gas:	No
Control Device:	N/A
Basis of Emission Estimates:	GRI-GLYCalc 4.0

Actual Pump Fuel/Glycol Circulation:

0.0277 * Pump Fuel Rate (scf/gal) * Temp. (°R)/Pressure (psia) =

0.0821

EMISSION ESTIMATES:

Emission estimates are taken from GRI-GLYCalc Version 4.0 Aggregate Calculations Report in Appendix C. The vapors from the condenser are based on 100% recycle/recompression control.

EMISSIONS SUMMARY (additional burner stack emissions):

POLLUTANT:	CALCULATED EMISSION RATES:	
	Hourly (lb/hr)	Annual (TPY)
Carbon Dioxide (excluded from VOC total)	0.0000	0.0000
Hydrogen Sulfide (toxic component, excluded from VOC total)	0.0000	0.0000
Methane (excluded from VOC total)	0.0362	0.1586
Ethane (excluded from VOC total)	0.0283	0.1240
Propane	0.0906	0.3968
Iso-Butane	0.0428	0.1875
N-Butane	0.0727	0.3184
Iso-Pentane	0.0273	0.1196
N-Pentane	0.0267	0.1169

POLLUTANT:	CALCULATED EMISSION RATES:	
	Hourly (lb/hr)	Annual (TPY)
N-Hexane (TAP)	0.0594	0.2602
Cyclohexane	0.0000	0.0000
Other Hexanes	0.0000	0.0000
Heptanes	0.0000	0.0000
Methylcyclohexane	0.0000	0.0000
2,2,4-Trimethylpentane (TAP)	0.0000	0.0000
Benzene (TAP)	0.0000	0.0000
Toluene (TAP)	0.0000	0.0000
Ethylbenzene (TAP)	0.0000	0.0000
Xylenes (TAP)	0.0000	0.0000
C8+ Heavies	0.0000	0.0000
Total Emissions	0.38	1.68
Total Hydrocarbon Emissions	0.38	1.68
Total VOC Emissions	0.32	1.40
Total TAP Emissions	0.06	0.26
Total Non VOC & Non TAP-HC	0.06	0.28
Total BTEX Emissions	0.00	0.00

Emission Calculations

POINT SOURCE I.D. NUMBER: 14-21-ICE-ES

EMISSION SOURCE DESCRIPTION: Internal Combustion Engine-Exhaust Stack
(Caterpillar G3306; Gas Compressor)

DATA:

Emission Source:	Internal Combustion Engine
Make/Model/Type:	Caterpillar/G3306/4-Stroke Rich Burn
Annual Hours of Operation:	8760
Maximum HP @ 1800-rpms: (provided by operator)	203
Brake Specific Fuel Consumption: (BTU/BHP-Hr; from manuf. Specs.)	7,877
VOC Weight % of Fuel Gas:	17.8
Fuel Gas Heat Rating: (BTU/scf; taken from actual wet gas analysis)	1201
Max. H ₂ S Concentration in Fuel Gas (ppmv):	0
Fuel Source:	Field Gas

Max. Hourly Energy Output (HP-Hr) = HP Rating x 1-hour = 203

Max. Annual Energy Output (HP-Hr/Yr) = HP Rating x Annual Operating Hours = 1,778,280

EMISSION FACTORS:

Unless otherwise noted, average emission factors were taken from GRI-HAPCalc ®3.01 for a 4-Stroke Rich-Burn Engine, using the "GRI Field Test Data" emission factor set.

HAP compounds with emission factors less than 0.001 gms/bhp-hr are not reported.

PM₁₀, PM_{2.5}, 1,3-Butadiene, Acetaldehyde, Acrolein & PAH emission factors are taken from Chapter 3.2 of AP-42, 5th Edition, Supplement F, July 2000 for large bore natural gas-fired internal combustion engines; using brake specific fuel consumption (BSFC) noted above.

SO₂ emission factor based on 100% conversion of sulfur compounds in fuel gas, using H₂S fuel composition noted above.

VOC & Formaldehyde emission factors are taken from manufacturers specs; refer to appendix C.

NOx & CO emission factors comply with emission standards established in 430 TAC 117.2000 Mass emissions cap and trade.

EMISSION CALCULATIONS:

POLLUTANT:	UNCONTROLLED EMISSION FACTOR (Grams/BHP-Hr)	CALCULATED EMISSION RATES:		
		Average Hourly (lb/hr):	Maximum Hourly (lb/hr):	Annual (TPY):
PM ₁₀ (filterable + condensable)	0.0694	0.0310	0.0310	0.1359
PM _{2.5} (filterable + condensable)	0.0694	0.0310	0.0310	0.1359
Sulfur Dioxide	0.0000	0.0000	0.0000	0.0000
Nitrogen Oxides	0.5000	0.2238	0.2238	0.9801
Carbon Monoxide	3.0000	1.3426	1.3426	5.8807
NMEHC (expressed as VOC)	0.2600	0.1164	0.1164	0.5097
1,3-Butadiene (TAP)	0.0024	0.0011	0.0011	0.0046
Acetaldehyde (TAP)	0.0100	0.0045	0.0045	0.0195
Acrolein (TAP)	0.0094	0.0042	0.0042	0.0184
Benzene (TAP)	0.0221	0.0099	0.0099	0.0433
Formaldehyde (TAP)	0.1500	0.0671	0.0671	0.2940

POLLUTANT:	UNCONTROLLED EMISSION FACTOR (Grams/BHP-Hr)	CALCULATED EMISSION RATES:		
		Average Hourly (lb/hr):	Maximum Hourly (lb/hr):	Annual (TPY):
Methanol (TAP)	0.0067	0.0030	0.0030	0.0131
PAH (TAP)	0.0005	0.0002	0.0002	0.0010
Toluene (TAP)	0.0071	0.0032	0.0032	0.0139
Xylenes (TAP)	0.0017	0.0008	0.0008	0.0033
Total TAPs		0.09	0.09	0.41
Total VOC-TAPs		0.09	0.09	0.41
Total VOC		0.12	0.12	0.51

Emission Calculations

POINT SOURCE I.D. NUMBER:

15-21-BV

EMISSION SOURCE DESCRIPTION:

Blowcase Vessel (Compressor Skid Fluids)

DATA:

Emission Source:	Natural Gas Supplied to Blowcase
Blowcase Capacity (Gallons):	12
Approximate Volume Discharged per Dump Cycle (Gallons):	6.0
Maximum Annual Discharge Volume (Gallons):	29,200
Maximum Number of Annual Cycles:	4,867
Maximum Number of Cycles Per Hour:	2
Maximum Discharge Pressure (PSIA):	65
Operating Pressure During Filling Cycle (PSIA):	15
Gas Consumption Rate (SCF/Cycle): (difference in standard gas volumes under Discharge & Filling conditions)	5
Fuel Gas Specific Gravity (SG): (based on a representative wet gas analysis)	0.713
Basis of Estimates:	Mass Balance

Avg. Hourly Uncontrolled Supply Gas Emissions (lb/hr)	=	Cycles/Yr*Gas Rate*SG*0.0764/8760	=	0.15
Max. Hourly Uncontrolled Supply Gas Emissions (lb/hr)	=	Max. Cycles/Hr * Hourly Rate	=	0.30
Annual Potential Uncontrolled Supply Gas Emissions (TPY)	=	Hourly Rate *8760/2000	=	0.66


SPECIATION FACTORS:

Speciation of the supply gas is based on a representative wet gas analysis; refer to Southcross Energy Report No. 24-7077-24 in Appx C.

EMISSIONS SUMMARY:

POLLUTANT:	Weight Percent	CALCULATED EMISSION RATES		
		Average Hourly (lb/hr)	Maximum Hourly (lb/hr)	Annual (TPY)
Nitrogen (excluded from VOC total)	0.206	0.0003	0.0006	0.0014
Carbon Dioxide (excluded from VOC total)	2.615	0.0039	0.0078	0.0173
Methane (excluded from VOC total)	64.175	0.0963	0.1925	0.4236
Ethane (excluded from VOC total)	10.671	0.0160	0.0320	0.0704
Hydrogen Sulfide (excluded from VOC total)	0.000	0.0000	0.0000	0.0000
Propane	12.137	0.0182	0.0364	0.0801
Iso-Butane	3.196	0.0048	0.0096	0.0211
N-Butane	3.679	0.0055	0.0110	0.0243
Iso-Pentane	1.167	0.0018	0.0035	0.0077
N-Pentane	0.824	0.0012	0.0025	0.0054
Iso-Hexane	0.807	0.0012	0.0024	0.0053
N-Hexane (TAP)	0.187	0.0003	0.0006	0.0012
Methylcyclopentane	0.000	0.0000	0.0000	0.0000
Benzene (TAP)	0.038	0.0001	0.0001	0.0003
Cyclohexane	0.000	0.0000	0.0000	0.0000

POLLUTANT:	Weight Percent	CALCULATED EMISSION RATES		
		Average Hourly (lb/hr)	Maximum Hourly (lb/hr)	Annual (TPY)
Heptanes	0.101	0.0002	0.0003	0.0007
Methylcyclohexane	0.000	0.0000	0.0000	0.0000
Toluene (TAP)	0.039	0.0001	0.0001	0.0003
2,2,4-Trimethylpentane (TAP)	0.045	0.0001	0.0001	0.0003
Octanes	0.102	0.0002	0.0003	0.0007
Ethylbenzene (TAP)	0.002	0.0000	0.0000	0.0000
Xylenes (TAP)	0.011	0.0000	0.0000	0.0001
Nonanes	0.000	0.0000	0.0000	0.0000
Decanes Plus	0.000	0.0000	0.0000	0.0000
Total Weight Percent:	100.00			
Total TAP Emissions		0.00	0.00	0.00
Total VOC Emissions		0.03	0.07	0.15
Total Non VOC & Non TAP-HC		0.11	0.22	0.49
Total Emissions		0.15	0.30	0.66




Data use subject to license.

© DeLorme. Topo North America™ 9.

www.delorme.com




Scale 1 : 100,000



1" = 1.58 mi


Data Zoom 11-0



Data use subject to license.

© DeLorme. Topo North America™ 9.

www.delorme.com



Analysis ID: 24-7077-24

Alternate ID:

Use Contract Values: No

Name Hillcorp (B# #1- Hite #5)
Custody Meter

Company Name: Southcross Energy

Effective Date:	06/01/2015 09:00	Saturated HV:	1207.2	Sample Date:	06/15/2015
Valid Thru Date:	12/31/2078 00:00	As Del. HV:		Sample ID:	
Last Update:	07/06/2015 12:43	Dry HV:	1228.1	Sample Type:	Spot
Data Acquisition:		Measured HV:		Sample Pressure Base:	14.730
Data Source:	Lab Analysis	WOBSE:	1454.2	Sample Temperature:	86.0
Real Relative	0.7132	Water Content:		Sample Pressure:	490.0
Status:	Active			Lab Code:	

Component	% Mol	GPM
Methane	82.3460	
Ethane	7.3050	1.9598
Propane	5.6660	1.5659
I Butane	1.1320	0.3716
N Butane	1.3030	0.4121
I Pentane	0.3330	0.1222
N Pentane	0.2350	0.0855
Hexanes +	0.3020	0.1322

Nitrogen	0.1510
CO2	1.2230
Oxygen	0.0040
H2O	0.0000
CO	0.0000
H2S	0.0000
Hydrogen	0.0000
Helium	0.0000
Argon	0.0000

Total	100.0000	4.6493
-------	----------	--------

Sample Comments:

Configuration Comments:

COMPONENT	mole %	MOLE FRACTION	MW	fuel weight	WT frac	Wt %	dh*	Heat Value (BTU/SCF)	Carbon Weight %	C-H
Nitrogen	0.1510	0.002	28.0134	0.04	0.0021	0.2055	0	0.00	0.0000	0
Hydrogen Sulfide	0.0000	0.000	34.08	0.00	0.0000	0.0000	637.1	0.00	0.0000	0
Carbon Dioxide	1.2230	0.012	44.01	0.54	0.0261	2.6146	0	0.00	0.1469	0
Methane	82.3460	0.823	16.043	13.21	0.6417	64.1747	1010	831.69	9.8817	0.25
Ethane	7.3050	0.073	30.07	2.20	0.1067	10.6706	1770	129.27	1.7529	0.33333
Propane	5.6660	0.057	44.097	2.50	0.1214	12.1373	2516	142.56	2.0401	0.375
I-Butane	1.1320	0.011	58.123	0.66	0.0320	3.1962	3252	36.81	0.5434	0.4
N-Butane	1.3030	0.013	58.123	0.76	0.0368	3.6790	3262	42.51	0.6255	0.4
I-Pentane	0.3330	0.003	72.15	0.24	0.0117	1.1671	4001	13.32	0.1998	0.41667
N-Pentane	0.2350	0.002	72.15	0.17	0.0082	0.8236	4009	9.42	0.1410	0.41667
Other hexanes	0.1928	0.002	86.177	0.17	0.0081	0.8072	4750	9.16	0.1388	0.42857
N-hexane	0.0447	0.000	86.177	0.04	0.0019	0.1870	4756	2.12	0.0322	0.42857
heptane	0.0207	0.000	100.204	0.02	0.0010	0.1010	5503	1.14	0.0174	0.4375
iso-octane	0.0081	0.000	114.231	0.01	0.0004	0.0447	6232	0.50	0.0077	0.4444
octanes+	0.0145	0.000	144.231	0.02	0.0010	0.1016	6500	0.94	0.0174	0.4444
benzene	0.0100	0.000	78.114	0.01	0.0004	0.0379	3742	0.37	0.0072	1
toluene	0.0086	0.000	92.141	0.01	0.0004	0.0385	4475	0.39	0.0072	0.875
ethylbenzene	0.0004	0.000	106.167	0.00	0.0000	0.0022	5222	0.02	0.0004	0.8
xylene	0.0022	0.000	106.167	0.00	0.0001	0.0112	5209	0.11	0.0021	0.8
TOTALS	100.00	1.000		20.59	1.0000	100.0000		1220	15.5617	
hexanes+	0.3020			sg	0.7098					
				VOC wt%	22.3346		Carbon wt%	75.59487		
				Toxic wt%	0.3216					

Norcen Pump Circulation

FUNCTIONAL TABLES

CIRCULATION RATE — Gallons/Hour


$$Q(\text{GPM}) = (0.0277) \times \frac{1}{\text{gpm}} \times (T + 460) \times (P + 14.7)$$

Model Number	* Pump Speed — Strokes/Minute. Count one stroke for each discharge of pump.																		
	8	10	12	14	16	18	20	22	24	26	28	30	32	34	36	38	40		
1715 PV	8	10	12	14	16	18	20	22	24	26	28	30	32	34	36	38	40		
4015 PV	12	14	16	18	20	22	24	26	28	30	32	34	36	38	40	
9015 PV	27.5	27	31.5	36	40.5	45	49.5	54	58.5	63	67.5	72	76.5	81	85.5	90
21015 PV	166	79	92	105	118	131	144	157	171	184	197	210
45015 PV	166	200	233	266	300	333	366	400	433	466

*It is not recommended to attempt to run pumps at speeds less or greater than those indicated in the above table.

GAS CONSUMPTION

Operating Pressure—p.s.i.g.	300	400	500	600	700	800	900	1000	1100	1200	1300	1400	1500
Cu. Ft./Gallon @ 14.4 & 60°F.	1.7	2.3	2.8	3.4	3.9	4.5	5.0	5.6	6.1	6.7	7.2	7.9	8.3



Note: $1.9 \times 2.3759 \times 10^5 = 1616a$

Model Number "PV" Series "SC" Series	Dimensions, Inches													
	A	B	C	D	E	F	G	H	J	K	L	M	N	P
1715 PV	5 1/4	5 1/4	5 1/4	3 1/4	1 1/2	3 1/2	7 1/4	10 1/4	10 3/4	9 3/4	15	2 1/4	1 1/2	3
4015 PV & 2015 SC	5 1/4	5 1/4	5 1/4	3 1/4	1 1/2	3 1/2	7 1/4	10 1/4	10 3/4	9 3/4	15	2 1/4	1 1/2	3
9015 PV & 5015 SC	6 1/4	8 1/2 ± 1/4	6 3/4	5	1 1/2	4 1/2	8 1/4	13 1/4	13 3/4	11 3/4	20	2 1/2	2	3
21015 PV & 10015 SC	7 1/4	10 1/4 ± 1/4	7	5 3/4	2 1/2	5 1/2	9 1/4	14 1/4	16 3/4	13	24	3 3/4	2 1/2	4
45015 PV & 20015 SC	10 1/4	14 ± 1/4	9	6 3/4	2 1/2	6 1/2	11 3/4	19	21 1/4	16 3/4	34	3 3/4	3 1/2	6

Model Number	Max. Cap.		Size of Pipe Connections	Mounting Bolts	Approx. Weight
	G.P.M.	G.P.H.			
1715 PV	.67	40	1/2" N.P.T.	3/4" Dia.	66 lbs.
4015 PV	.67	40	1/2" N.P.T.	3/4" Dia.	66 lbs.
9015 PV	1.5	90	3/4" N.P.T.	1/2" Dia.	119 lbs.
21015 PV	3.5	210	1" N.P.T.	1/2" Dia.	215 lbs.
45015 PV	15	150	1 1/2" N.P.T.	1/2" Dia.	500 lbs.

GRI-GLYCalc VERSION 4.0 - SUMMARY OF INPUT VALUES

Case Name: gglycol unit

File Name:

Date: May 06, 2021

DESCRIPTION:

Description: 1.5 MMSCFD

Annual Hours of Operation: 8760.0 hours/yr

WET GAS:

Temperature: 86.00 deg. F

Pressure: 500.00 psig

Wet Gas Water Content: Saturated

Component	Conc. (vol %)
Carbon Dioxide	1.2230
Nitrogen	0.1510
Methane	82.3460
Ethane	7.3050
Propane	5.6660
Isobutane	1.1320
n-Butane	1.3030
Isopentane	0.3330
n-Pentane	0.2350
Other Hexanes	0.3020

DRY GAS:

Flow Rate: 1.5 MMSCF/day
Water Content: 7.0 lbs. H2O/MMSCF

LEAN GLYCOL:

Glycol Type: TEG
Water Content: 1.5 wt% H2O
Recirculation Ratio: 3.0 gal/lb H2O

PUMP:

Glycol Pump Type: Gas Injection

Gas Injection Pump Volume Ratio: 0.082 acfm gas/gpm glycol

FLASH TANK:

Flash Control: Recycle/recompression
Temperature: 80.0 deg. F
Pressure: 110.0 psig

REGENERATOR OVERHEADS CONTROL DEVICE:

Control Device: Condenser
Temperature: 80.0 deg. F
Pressure: 110.0 psia

GRI-GLYCalc VERSION 4.0 - AGGREGATE CALCULATIONS REPORT

Case Name: gglycol unit

File Name:

Date: May 06, 2021

DESCRIPTION:

Description: 1.5 MMSCFD

Annual Hours of Operation: 8760.0 hours/yr

EMISSIONS REPORTS:

CONTROLLED REGENERATOR EMISSIONS

Component	lbs/hr	lbs/day	tons/yr
Methane	0.0354	0.850	0.1551
Ethane	0.0260	0.623	0.1137
Propane	0.0659	1.581	0.2886
Isobutane	0.0234	0.562	0.1026
n-Butane	0.0337	0.809	0.1477
Isopentane	0.0073	0.176	0.0322
n-Pentane	0.0056	0.134	0.0245
Other Hexanes	0.0064	0.153	0.0280
Total Emissions	0.2037	4.889	0.8923

Total Hydrocarbon Emissions 0.2037 4.889 0.8923

Total VOC Emissions 0.1424 3.417 0.6236

UNCONTROLLED REGENERATOR EMISSIONS

Component	lbs/hr	lbs/day	tons/yr
Methane	0.0362	0.869	0.1586
Ethane	0.0283	0.679	0.1239
Propane	0.0906	2.175	0.3969
Isobutane	0.0428	1.026	0.1873
n-Butane	0.0727	1.744	0.3183
Isopentane	0.0273	0.656	0.1197
n-Pentane	0.0267	0.642	0.1172
Other Hexanes	0.0594	1.425	0.2600
Total Emissions	0.3840	9.216	1.6818

Total Hydrocarbon Emissions 0.3840 9.216 1.6818

FLASH GAS EMISSIONS

Note: Flash Gas Emissions are zero with the
Recycle/recompression control option.

FLASH TANK OFF GAS

Component	lbs/hr	lbs/day	tons/yr
Methane	1.2975	31.140	5.6830
Ethane	0.2575	6.179	1.1277
Propane	0.3277	7.864	1.4352
Isobutane	0.0927	2.225	0.4061
n-Butane	0.1139	2.733	0.4987
Isopentane	0.0351	0.841	0.1536
n-Pentane	0.0261	0.625	0.1141
Other Hexanes	0.0400	0.960	0.1753
Total Emissions	2.1903	52.568	9.5937
Total Hydrocarbon Emissions	2.1903	52.568	9.5937
Total VOC Emissions	0.6354	15.249	2.7830

COMBINED REGENERATOR VENT/FLASH GAS EMISSIONS

Component	lbs/hr	lbs/day	tons/yr
Methane	0.0354	0.850	0.1551
Ethane	0.0260	0.623	0.1137
Propane	0.0659	1.581	0.2886
Isobutane	0.0234	0.562	0.1026
n-Butane	0.0337	0.809	0.1477
Isopentane	0.0073	0.176	0.0322
n-Pentane	0.0056	0.134	0.0245
Other Hexanes	0.0064	0.153	0.0280
Total Emissions	0.2037	4.889	0.8923
Total Hydrocarbon Emissions	0.2037	4.889	0.8923
Total VOC Emissions	0.1424	3.417	0.6236

COMBINED REGENERATOR VENT/FLASH GAS EMISSION CONTROL REPORT:

Component	Uncontrolled tons/yr	Controlled tons/yr	% Reduction
Methane	5.8416	0.1551	97.35
Ethane	1.2516	0.1137	90.92
Propane	1.8321	0.2886	84.25
Isobutane	0.5934	0.1026	82.71
n-Butane	0.8171	0.1477	81.92
Isopentane	0.2733	0.0322	88.22
n-Pentane	0.2313	0.0245	89.42
Other Hexanes	0.4353	0.0280	93.57
Total Emissions	11.2755	0.8923	92.09
Total Hydrocarbon Emissions	11.2755	0.8923	92.09
Total VOC Emissions	4.1823	0.6236	85.09

EQUIPMENT REPORTS:

CONDENSER

Condenser Outlet Temperature: 80.00 deg. F
 Condenser Pressure: 110.00 psia
 Condenser Duty: 8.20e-003 MM BTU/hr
 Hydrocarbon Recovery: 0.01 bbls/day
 Produced Water: 0.26 bbls/day
 VOC Control Efficiency: 55.44 %
 HAP Control Efficiency: 0.00 %
 BTEX Control Efficiency: 0.00 %
 Dissolved Hydrocarbons in Water: 242.00 mg/L

Component	Emitted	Condensed
Water	0.02%	99.98%
Carbon Dioxide	85.28%	14.72%
Nitrogen	99.48%	0.52%
Methane	97.80%	2.20%
Ethane	91.76%	8.24%
Propane	72.71%	27.29%
Isobutane	54.79%	45.21%
n-Butane	46.40%	53.60%
Isopentane	26.89%	73.11%
n-Pentane	20.89%	79.11%
Other Hexanes	10.77%	89.23%

ABSORBER ---

NOTE: Because the Calculated Absorber Stages was below the minimum allowed, GRI-GLYCalc has set the number of Absorber Stages to 1.25 and has calculated a revised Dry Gas Dew Point.

Calculated Absorber Stages: 1.25
 Calculated Dry Gas Dew Point: 4.79 lbs. H₂O/MMSCF

Temperature: 86.0 deg. F
 Pressure: 500.0 psig
 Dry Gas Flow Rate: 1.5000 MMSCF/day
 Glycol Losses with Dry Gas: 0.0057 lb/hr
 Wet Gas Water Content: Saturated
 Calculated Wet Gas Water Content: 65.79 lbs. H₂O/MMSCF
 Specified Lean Glycol Recirc. Ratio: 3.00 gal/lb H₂O

Component	Remaining in Dry Gas	Absorbed in Glycol
Water	7.28%	92.72%
Carbon Dioxide	99.89%	0.11%
Nitrogen	99.99%	0.01%
Methane	99.99%	0.01%
Ethane	99.98%	0.02%
Propane	99.95%	0.05%
Isobutane	99.93%	0.07%
n-Butane	99.90%	0.10%
Isopentane	99.90%	0.10%
n-Pentane	99.87%	0.13%
Other Hexanes	99.82%	0.18%

FLASH TANK ---

Flash Control: Recycle/recompression
 Flash Temperature: 80.0 deg. F
 Flash Pressure: 110.0 psig

Component	Left in Glycol	Removed in Flash Gas
Water	99.98%	0.02%
Carbon Dioxide	32.60%	67.40%
Nitrogen	2.56%	97.44%
Methane	2.71%	97.29%
Ethane	9.90%	90.10%
Propane	21.66%	78.34%
Isobutane	31.56%	68.44%
n-Butane	38.96%	61.04%

Isopentane	43.99%	56.01%
n-Pentane	50.83%	49.17%
Other Hexanes	60.04%	39.96%

REGENERATOR

No Stripping Gas used in regenerator.

Component	Remaining in Glycol	Distilled Overhead
Water	28.89%	71.11%
Carbon Dioxide	0.00%	100.00%
Nitrogen	0.00%	100.00%
Methane	0.00%	100.00%
Ethane	0.00%	100.00%
Propane	0.00%	100.00%
Isobutane	0.00%	100.00%
n-Butane	0.00%	100.00%
Isopentane	0.75%	99.25%
n-Pentane	0.70%	99.30%
Other Hexanes	1.28%	98.72%

STREAM REPORTS:

WET GAS STREAM

Temperature: 86.00 deg. F
Pressure: 514.70 psia
Flow Rate: 6.26e+004 scfh

Component	Conc. (vol%)	Loading (lb/hr)
Water	1.39e-001	4.12e+000
Carbon Dioxide	1.22e+000	8.87e+001
Nitrogen	1.51e-001	6.97e+000
Methane	8.22e+001	2.18e+003
Ethane	7.30e+000	3.62e+002
Propane	5.66e+000	4.12e+002
Isobutane	1.13e+000	1.08e+002
n-Butane	1.30e+000	1.25e+002
Isopentane	3.33e-001	3.96e+001
n-Pentane	2.35e-001	2.79e+001

Other Hexanes 3.02e-001 4.29e+001

Total Components 100.00 3.39e+003

DRY GAS STREAM

Temperature: 86.00 deg. F

Pressure: 514.70 psia

Flow Rate: 6.25e+004 scfh

Component	Conc.	Loading
	(vol%)	(lb/hr)

Water 1.01e-002 3.00e-001

Carbon Dioxide 1.22e+000 8.86e+001

Nitrogen 1.51e-001 6.97e+000

Methane 8.23e+001 2.18e+003

Ethane 7.30e+000 3.62e+002

Propane 5.66e+000 4.11e+002

Isobutane 1.13e+000 1.08e+002

n-Butane 1.30e+000 1.25e+002

Isopentane 3.33e-001 3.95e+001

n-Pentane 2.35e-001 2.79e+001

Other Hexanes 3.01e-001 4.28e+001

Total Components 100.00 3.39e+003

LEAN GLYCOL STREAM

Temperature: 86.00 deg. F

Flow Rate: 1.84e-001 gpm

Component	Conc.	Loading
	(wt%)	(lb/hr)

TEG 9.85e+001 1.02e+002

Water 1.50e+000 1.55e+000

Carbon Dioxide 9.36e-012 9.69e-012

Nitrogen 4.99e-014 5.16e-014

Methane 4.97e-018 5.15e-018

Ethane 4.08e-008 4.22e-008

Propane 7.67e-009 7.94e-009

Isobutane 2.22e-009 2.30e-009

n-Butane 2.85e-009 2.95e-009

Isopentane 1.99e-004 2.06e-004

n-Pentane 1.83e-004 1.89e-004

Other Hexanes 7.43e-004 7.69e-004

RICH GLYCOL AND PUMP GAS STREAM

Temperature: 86.00 deg. F
Pressure: 514.70 psia
Flow Rate: 1.97e-001 gpm
NOTE: Stream has more than one phase.

Component	Conc. (wt%)	Loading (lb/hr)
TEG	9.26e+001	1.02e+002
Water	4.89e+000	5.37e+000
Carbon Dioxide	1.32e-001	1.45e-001
Nitrogen	3.91e-003	4.30e-003
Methane	1.21e+000	1.33e+000
Ethane	2.60e-001	2.86e-001
Propane	3.80e-001	4.18e-001
Isobutane	1.23e-001	1.35e-001
n-Butane	1.70e-001	1.87e-001
Isopentane	5.69e-002	6.26e-002
n-Pentane	4.82e-002	5.30e-002
Other Hexanes	9.11e-002	1.00e-001
Total Components	100.00	1.10e+002

FLASH TANK OFF GAS STREAM

Temperature: 80.00 deg. F
Pressure: 124.70 psia
Flow Rate: 3.95e+001 scfh

Component	Conc. (vol%)	Loading (lb/hr)
Water	4.72e-002	8.85e-004
Carbon Dioxide	2.13e+000	9.77e-002
Nitrogen	1.43e-001	4.19e-003
Methane	7.77e+001	1.30e+000
Ethane	8.22e+000	2.57e-001
Propane	7.13e+000	3.28e-001
Isobutane	1.53e+000	9.27e-002
n-Butane	1.88e+000	1.14e-001
Isopentane	4.67e-001	3.51e-002
n-Pentane	3.47e-001	2.61e-002
Other Hexanes	4.46e-001	4.00e-002
Total Components	100.00	2.29e+000

FLASH TANK GLYCOL STREAM

Temperature: 80.00 deg. F

Flow Rate: 1.92e-001 gpm

Component	Conc. (wt%)	Loading (lb/hr)
TEG	9.46e+001	1.02e+002
Water	4.99e+000	5.37e+000
Carbon Dioxide	4.39e-002	4.73e-002
Nitrogen	1.02e-004	1.10e-004
Methane	3.36e-002	3.62e-002
Ethane	2.63e-002	2.83e-002
Propane	8.42e-002	9.06e-002
Isobutane	3.97e-002	4.28e-002
n-Butane	6.75e-002	7.27e-002
Isopentane	2.56e-002	2.75e-002
n-Pentane	2.50e-002	2.69e-002
Other Hexanes	5.58e-002	6.01e-002
Total Components	100.00	1.08e+002

FLASH GAS EMISSIONS

Control Method: Recycle/recompression

Control Efficiency: 100.00

Note: Flash Gas Emissions are zero with the
Recycle/recompression control option.

REGENERATOR OVERHEADS STREAM

Temperature: 212.00 deg. F

Pressure: 14.70 psia

Flow Rate: 8.42e+001 scfh

Component	Conc. (vol%)	Loading (lb/hr)
Water	9.56e+001	3.82e+000
Carbon Dioxide	4.84e-001	4.73e-002
Nitrogen	1.77e-003	1.10e-004
Methane	1.02e+000	3.62e-002
Ethane	4.24e-001	2.83e-002
Propane	9.26e-001	9.06e-002
Isobutane	3.32e-001	4.28e-002

Page: 9

n-Butane 5.64e-001 7.27e-002
Isopentane 1.71e-001 2.73e-002
n-Pentane 1.67e-001 2.67e-002

Other Hexanes 3.10e-001 5.94e-002

Total Components 100.00 4.25e+000

CONDENSER VENT GAS STREAM

Temperature: 80.00 deg. F
Pressure: 110.00 psia
Flow Rate: 2.56e+000 scfh

Component	Conc. (vol%)	Loading (lb/hr)
Water	4.78e-001	5.81e-004
Carbon Dioxide	1.36e+001	4.03e-002
Nitrogen	5.79e-002	1.10e-004
Methane	3.27e+001	3.54e-002
Ethane	1.28e+001	2.60e-002
Propane	2.21e+001	6.59e-002
Isobutane	5.97e+000	2.34e-002
n-Butane	8.59e+000	3.37e-002
Isopentane	1.51e+000	7.35e-003
n-Pentane	1.15e+000	5.59e-003
Other Hexanes	1.10e+000	6.39e-003

Total Components	100.00	2.45e-001

CONDENSER PRODUCED WATER STREAM

Temperature: 80.00 deg. F
Flow Rate: 7.65e-003 gpm

Component	Conc. (wt%)	Loading (lb/hr)	(ppm)
Water	9.98e+001	3.82e+000	998343.
Carbon Dioxide	1.42e-001	5.41e-003	1415.
Nitrogen	8.04e-006	3.07e-007	0.
Methane	5.36e-003	2.05e-004	54.
Ethane	4.82e-003	1.84e-004	48.
Propane	8.08e-003	3.09e-004	81.
Isobutane	1.58e-003	6.03e-005	16.
n-Butane	3.14e-003	1.20e-004	31.
Isopentane	4.92e-004	1.88e-005	5.
n-Pentane	4.13e-004	1.58e-005	4.

Other Hexanes 3.17e-004 1.21e-005 3.

Total Components 100.00 3.83e+000 1000000.

CONDENSER RECOVERED OIL STREAM

Temperature: 80.00 deg. F

Flow Rate: 4.25e-004 gpm

Component	Conc. (wt%)	Loading (lb/hr)
-----------	----------------	--------------------

Water 5.89e-002 1.07e-004

Carbon Dioxide 8.50e-001 1.54e-003

Nitrogen 1.47e-004 2.66e-007

Methane 3.28e-001 5.93e-004

Ethane 1.19e+000 2.15e-003

Propane 1.35e+001 2.44e-002

Isobutane 1.06e+001 1.93e-002

n-Butane 2.15e+001 3.88e-002

Isopentane 1.10e+001 2.00e-002

n-Pentane 1.17e+001 2.11e-002

Other Hexanes 2.93e+001 5.30e-002

Total Components 100.00 1.81e-001

ENGINE SPEED (rpm):	1800	FUEL:	Nat Gas
COMPRESSION RATIO:	8.0:1	FUEL SYSTEM:	HPG IMPCO
AFTERCOOLER WATER INLET (°F):	130	FUEL PRESSURE RANGE(psig):	12.0-24.9
JACKET WATER OUTLET (°F):	210	FUEL METHANE NUMBER:	80
ASPIRATION:	TA	FUEL LHV (Btu/scf):	905
COOLING SYSTEM:	JW+OC, AC	ALTITUDE CAPABILITY AT 77°F INLET AIR TEMP, (ft):	1500
IGNITION SYSTEM:	MAG	APPLICATION:	Gas Compression
EXHAUST MANIFOLD:	WC		
COMBUSTION:	Standard Setting		
EXHAUST OXYGEN (% O ₂):	2.0		

	RATING	NOTES	LOAD	100%	75%	50%
ENGINE POWER	(WITHOUT FAN)	(1)	bhp	203	152	102
ENGINE EFFICIENCY	(ISO 3046/1)	(2)	%	32.3	30.1	27.6
ENGINE EFFICIENCY	(NOMINAL)	(2)	%	32.3	30.1	27.6

ENGINE DATA						
FUEL CONSUMPTION	(ISO 3046/1)	(3)	Btu/bhp-hr	7877	8454	9233
FUEL CONSUMPTION	(NOMINAL)	(3)	Btu/bhp-hr	7877	8454	9233
AIR FLOW (77°F, 14.7 psia)	(WET)	(4) (5)	scfm	320	259	192
AIR FLOW	(WET)	(4) (5)	lb/hr	1420	1149	853
COMPRESSOR OUT PRESSURE			in Hg(abs)	43.9	41.2	34.4
COMPRESSOR OUT TEMPERATURE			°F	221	180	138
AFTERCOOLER AIR OUT TEMPERATURE			°F	135	131	131
INLET MAN. PRESSURE		(6)	in Hg(abs)	39.1	32.3	23.7
INLET MAN. TEMPERATURE	(MEASURED IN PLENUM)	(7)	°F	135	131	131
TIMING		(8)	°BTDC	34	34	34
EXHAUST TEMPERATURE - ENGINE OUTLET		(9)	°F	1004	972	932
EXHAUST GAS FLOW (@engine outlet temp, 14.5 psia)	(WET)	(10) (5)	ft ³ /min	973	769	554
EXHAUST GAS MASS FLOW	(WET)	(10) (5)	lb/hr	1501	1214	900

EMISSIONS DATA - ENGINE OUT						
NOx (as NO ₂)		(11)(12)	g/bhp-hr	27.71	23.47	20.70
CO		(11)(13)	g/bhp-hr	1.50	1.60	1.50
THC (mol. wt. of 15.84)		(11)(13)	g/bhp-hr	1.10	1.10	1.40
NMHC (mol. wt. of 15.84)		(11)(13)	g/bhp-hr	0.16	0.16	0.21
NMNEHC (VOCs) (mol. wt. of 15.84)		(11)(13)(14)	g/bhp-hr	0.11	0.11	0.14
HCHO (Formaldehyde)		(11)(13)	g/bhp-hr	0.15	0.15	0.18
CO ₂		(11)(13)	g/bhp-hr	515	553	604
EXHAUST OXYGEN		(11)(15)	% DRY	2.0	1.7	2.5
LAMBDA		(11)(15)		1.10	1.10	1.12

ENERGY BALANCE DATA						
LHV INPUT		(16)	Btu/min	26651	21453	15620
HEAT REJECTION TO JACKET WATER (JW)		(17)(22)	Btu/min	8557	7616	6109
HEAT REJECTION TO ATMOSPHERE		(18)	Btu/min	1066	858	625
HEAT REJECTION TO LUBE OIL (OC)		(19)(22)	Btu/min	1353	1204	966
HEAT REJECTION TO EXHAUST (LHV TO 77°F)		(20)	Btu/min	6509	5085	3589
HEAT REJECTION TO EXHAUST (LHV TO 350°F)		(20)	Btu/min	4556	3495	2416
HEAT REJECTION TO AFTERCOOLER (AC)		(21)(23)	Btu/min	557	252	28

CONDITIONS AND DEFINITIONS

Engine rating obtained and presented in accordance with ISO 3046/1. (Standard reference conditions of 77°F, 29.60 in Hg barometric pressure, 500 ft. altitude.) No overload permitted at rating shown. Consult the altitude deration factor chart for applications that exceed the rated altitude or temperature.

Emission levels are at engine exhaust flange prior to any after treatment. Values are based on engine operating at steady state conditions. Tolerances specified are dependent upon fuel quality. Fuel methane number cannot vary more than ± 3. Part load data may require engine adjustment.

For notes information consult page three.

FUEL USAGE GUIDE

CAT METHANE NUMBER	25	30	35	40	45	50	55	60	65	70	75	80	100
SET POINT TIMING	-	20	21	23	25	26	27	28	30	31	32	34	34
DERATION FACTOR	0	1	1	1	1	1	1	1	1	1	1	1	1

ALTITUDE DERATION FACTORS AT RATED SPEED

INLET AIR TEMP °F	0	1000	2000	3000	4000	5000	6000	7000	8000	9000	10000	11000	12000
130	0.96	0.93	0.89	0.86	0.83	0.80	0.77	0.74	0.71	0.68	0.65	0.63	0.60
120	0.98	0.94	0.91	0.87	0.84	0.81	0.78	0.75	0.72	0.69	0.66	0.64	0.61
110	1	0.96	0.92	0.89	0.86	0.82	0.79	0.76	0.73	0.70	0.67	0.65	0.62
100	1	0.98	0.94	0.91	0.87	0.84	0.81	0.77	0.74	0.72	0.69	0.66	0.63
90	1	1	0.96	0.92	0.89	0.85	0.82	0.79	0.76	0.73	0.70	0.67	0.64
80	1	1	0.98	0.94	0.90	0.87	0.84	0.80	0.77	0.74	0.71	0.68	0.66
70	1	1	0.99	0.96	0.92	0.89	0.85	0.82	0.79	0.76	0.73	0.70	0.67
60	1	1	1	0.98	0.94	0.90	0.87	0.83	0.80	0.77	0.74	0.71	0.68
50	1	1	1	0.99	0.96	0.92	0.89	0.85	0.82	0.79	0.75	0.72	0.69

ALTITUDE (FEET ABOVE SEA LEVEL)

AFTERCOOLER HEAT REJECTION FACTORS
(ACHRF)

INLET AIR TEMP °F	0	1000	2000	3000	4000	5000	6000	7000	8000	9000	10000	11000	12000
130	1.70	1.87	1.95	1.95	1.95	1.95	1.95	1.95	1.95	1.95	1.95	1.95	1.95
120	1.55	1.72	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80
110	1.41	1.57	1.65	1.65	1.65	1.65	1.65	1.65	1.65	1.65	1.65	1.65	1.65
100	1.26	1.42	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50
90	1.11	1.27	1.35	1.35	1.35	1.35	1.35	1.35	1.35	1.35	1.35	1.35	1.35
80	1	1.12	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20
70	1	1	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05
60	1	1	1	1	1	1	1	1	1	1	1	1	1
50	1	1	1	1	1	1	1	1	1	1	1	1	1

ALTITUDE (FEET ABOVE SEA LEVEL)

MINIMUM SPEED CAPABILITY AT THE RATED SPEED'S SITE TORQUE
(RPM)

INLET AIR TEMP °F	0	1000	2000	3000	4000	5000	6000	7000	8000	9000	10000	11000	12000
130	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1440	1500
120	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1420	1480
110	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1450
100	1350	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
90	1290	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
80	1220	1360	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
70	1200	1290	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
60	1200	1220	1360	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
50	1200	1200	1290	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400

ALTITUDE (FEET ABOVE SEA LEVEL)

FUEL USAGE GUIDE:

This table shows the derate factor required for a given fuel. Note that deration occurs as the methane number decreases. Methane number is a scale to measure detonation characteristics of various fuels. The methane number of a fuel is determined by using the Caterpillar Methane Number Calculation program.

ALTITUDE DERATION FACTORS:

This table shows the deration required for various air inlet temperatures and altitudes. Use this information along with the fuel usage guide chart to help determine actual engine power for your site.

ACTUAL ENGINE RATING:

To determine the actual rating of the engine at site conditions, one must consider separately, limitations due to fuel characteristics and air system limitations. The Fuel Usage Guide deration establishes fuel limitations. The Altitude/Temperature deration factors and RPC (reference the Caterpillar Methane Program) establish air system limitations. RPC comes into play when the Altitude/Temperature deration is less than 1.0 (100%). Under this condition, add the two factors together. When the site conditions do not require an Altitude/Temperature derate (factor is 1.0), it is assumed the turbocharger has sufficient capability to overcome the low fuel relative power, and RPC is ignored. To determine the actual power available, take the lowest rating between 1) and 2).

- 1) Fuel Usage Guide Deration
- 2) $1 - ((1 - \text{Altitude/Temperature Deration}) + (1 - \text{RPC}))$

AFTERCOOLER HEAT REJECTION FACTORS(ACHRF):

Aftercooler heat rejection is given for standard conditions of 77°F and 500 ft. altitude. To maintain a constant air inlet manifold temperature, as the inlet air temperature goes up, so must the heat rejection. As altitude increases, the turbocharger must work harder to overcome the lower atmospheric pressure. This increases the amount of heat that must be removed from the inlet air by the aftercooler. Use the aftercooler heat rejection factor (ACHRF) to adjust for inlet air temp and altitude conditions. See Notes 22 and 23 below for application of this factor in calculating the heat exchanger sizing criteria. Failure to properly account for these factors could result in detonation and cause the engine to shutdown or fail.

MINIMUM SPEED CAPABILITY AT THE RATED SPEED'S SITE TORQUE (RPM):

This table shows the minimum allowable engine turndown speed where the engine will maintain the Rated Speed's Torque for the given ambient conditions.

NOTES:

1. Engine rating is with two engine driven water pumps. Tolerance is $\pm 3\%$ of full load.
2. ISO 3046/1 engine efficiency tolerance is (+)0, (-)5% of full load % efficiency value. Nominal engine efficiency tolerance is $\pm 5.0\%$ of full load % efficiency value.
3. ISO 3046/1 fuel consumption tolerance is (+)5, (-)0% of full load data. Nominal fuel consumption tolerance is $\pm 5.0\%$ of full load data.
4. Air flow value is on a 'wet' basis. Flow is a nominal value with a tolerance of $\pm 5\%$.
5. Inlet and Exhaust Restrictions must not exceed A&I limits based on full load flow rates from the standard technical data sheet.
6. Inlet manifold pressure is a nominal value with a tolerance of $\pm 5\%$.
7. Inlet manifold temperature is a nominal value with a tolerance of $\pm 9^\circ\text{F}$.
8. Timing indicated is for use with the minimum fuel methane number specified. Consult the appropriate fuel usage guide for timing at other methane numbers.
9. Exhaust temperature is a nominal value with a tolerance of (+)63°F, (-)54°F.
10. Exhaust flow value is on a 'wet' basis. Flow is a nominal value with a tolerance of $\pm 6\%$.
11. Emissions data is at engine exhaust flange prior to any after treatment.
12. NOx values are "Not to Exceed".
13. CO, CO2, THC, NMHC, NMNEHC, and HCHO values are "Not to Exceed" levels. THC, NMHC, and NMNEHC do not include aldehydes.
14. VOCs - Volatile organic compounds as defined in US EPA 40 CFR 60, subpart JJJJ
15. Exhaust Oxygen tolerance is ± 0.5 .
16. LHV rate tolerance is $\pm 5.0\%$.
17. Heat rejection to jacket water value displayed includes heat to jacket water alone. Value is based on treated water. Tolerance is $\pm 10\%$ of full load data.
18. Heat rejection to atmosphere based on treated water. Tolerance is $\pm 50\%$ of full load data.
19. Lube oil heat rate based on treated water. Tolerance is $\pm 20\%$ of full load data.
20. Exhaust heat rate based on treated water. Tolerance is $\pm 10\%$ of full load data.
21. Heat rejection to aftercooler based on treated water. Tolerance is $\pm 5\%$ of full load data.
22. Total Jacket Water Circuit heat rejection is calculated as: $(JW \times 1.1) + (OC \times 1.2)$. Heat exchanger sizing criterion is maximum circuit heat rejection at site conditions, with applied tolerances. A cooling system safety factor may be multiplied by the total circuit heat rejection to provide additional margin.
23. Total Aftercooler Circuit heat rejection is calculated as: $AC \times \text{ACHRF} \times 1.05$. Heat exchanger sizing criterion is maximum circuit heat rejection at site conditions, with applied tolerances. A cooling system safety factor may be multiplied by the total circuit heat rejection to provide additional margin.

FREE FIELD MECHANICAL & EXHAUST NOISE**MECHANICAL: Sound Power (1/3 Octave Frequencies)**

Percent Load	Engine Power	Overall	100 Hz	125 Hz	160 Hz	200 Hz	250 Hz	315 Hz	400 Hz	500 Hz	630 Hz	800 Hz
%	bhp	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)
100	203	104.6	69.0	72.5	73.5	78.7	87.2	84.9	84.9	89.1	90.0	92.9
75	152	104.8	67.3	70.8	72.6	78.7	83.9	83.7	83.8	87.8	90.2	91.5
50	102	103.1	66.3	69.5	72.9	78.2	80.9	81.3	81.9	86.5	87.4	91.0

MECHANICAL: Sound Power (1/3 Octave Frequencies)

Percent Load	Engine Power	1 kHz	1.25 kHz	1.6 kHz	2 kHz	2.5 kHz	3.15 kHz	4 kHz	5 kHz	6.3 kHz	8 kHz	10 kHz
%	bhp	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)
100	203	93.4	98.1	95.8	94.5	94.3	92.5	92.3	91.0	88.7	86.9	83.8
75	152	98.7	97.5	94.9	92.9	93.7	91.7	92.3	90.0	88.3	84.8	81.5
50	102	90.9	97.9	93.3	92.2	93.5	91.1	91.1	89.5	86.1	83.0	77.6

EXHAUST: Sound Power (1/3 Octave Frequencies)

Percent Load	Engine Power	Overall	100 Hz	125 Hz	160 Hz	200 Hz	250 Hz	315 Hz	400 Hz	500 Hz	630 Hz	800 Hz
%	bhp	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)
100	203	114.2	98.9	88.1	93.3	100.4	100.1	99.2	101.4	105.0	104.0	104.6
75	152	114.3	97.2	91.3	99.8	106.4	101.3	101.8	102.1	103.7	103.4	104.0
50	102	112.5	95.6	90.1	98.2	105.0	101.5	100.1	102.1	101.6	101.4	101.7

EXHAUST: Sound Power (1/3 Octave Frequencies)

Percent Load	Engine Power	1 kHz	1.25 kHz	1.6 kHz	2 kHz	2.5 kHz	3.15 kHz	4 kHz	5 kHz	6.3 kHz	8 kHz	10 kHz
%	bhp	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)
100	203	104.0	103.7	103.1	103.1	102.4	100.1	97.5	91.1	81.1	69.3	59.4
75	152	103.8	102.8	102.0	102.2	100.2	97.4	94.2	87.8	77.8	66.7	60.0
50	102	102.3	100.7	99.0	98.6	96.0	92.7	89.0	82.2	71.9	64.9	47.8

SOUND PARAMETER DEFINITION:

Sound Power Level Data - DM8702-01

Sound power is defined as the total sound energy emanating from a source irrespective of direction or distance. Sound power level data is presented under two index headings:

Sound power level -- Mechanical

Sound power level -- Exhaust

Mechanical: Sound power level data is calculated in accordance with ISO 6798. The data is recorded with the exhaust sound source isolated.

Exhaust: Sound power level data is calculated in accordance with ISO 6798 Annex A.

Measurements made in accordance with ISO 6798 for engine and exhaust sound level only. No cooling system noise is included unless specifically indicated. Sound level data is indicative of noise levels recorded on one engine sample in a survey grade 3 environment.

How an engine is packaged, installed and the site acoustical environment will affect the site specific sound levels. For site specific sound level guarantees, sound data collection needs to be done on-site or under similar conditions.

05/07/21
10:24:10

*** SCREEN3 MODEL RUN ***
*** VERSION DATED 13043 ***

15-21-ICE

SIMPLE TERRAIN INPUTS:

SOURCE TYPE	=	POINT
EMISSION RATE (G/S)	=	0.300000E-01
STACK HEIGHT (M)	=	4.5700
STK INSIDE DIAM (M)	=	0.1500
STK EXIT VELOCITY (M/S)	=	25.1800
STK GAS EXIT TEMP (K)	=	813.0000
AMBIENT AIR TEMP (K)	=	297.0000
RECEPTOR HEIGHT (M)	=	1.5000
URBAN/RURAL OPTION	=	RURAL
BUILDING HEIGHT (M)	=	0.0000
MIN HORIZ BLDG DIM (M)	=	0.0000
MAX HORIZ BLDG DIM (M)	=	0.0000

THE REGULATORY (DEFAULT) MIXING HEIGHT OPTION WAS SELECTED.
THE REGULATORY (DEFAULT) ANEMOMETER HEIGHT OF 10.0 METERS WAS ENTERED.

BOUY. FLUX = 0.882 M**4/S**3; MOM. FLUX = 1.303 M**4/S**2.

*** FULL METEOROLOGY ***

*** SCREEN AUTOMATED DISTANCES ***

*** TERRAIN HEIGHT OF 0. M ABOVE STACK BASE USED FOR FOLLOWING DISTANCES ***

DIST (M)	CONC (UG/M**3)	STAB	U10M (M/S)	USTK (M/S)	MIX HT (M)	PLUME HT (M)	SIGMA Y (M)	SIGMA Z (M)	DWASH
10.	0.2916E-03	2	5.0	5.0	1600.0	8.47	2.38	1.32	NO
100.	11.92	3	3.5	3.5	1120.0	10.14	12.56	7.61	NO
200.	10.49	4	3.0	3.0	960.0	11.07	15.67	8.70	NO
300.	8.703	4	2.0	2.0	640.0	14.32	22.78	12.41	NO

MAXIMUM 1-HR CONCENTRATION AT OR BEYOND 10. M:									
76.	12.34	3	4.5	4.5	1440.0	8.90	9.86	5.99	NO

DWASH= MEANS NO CALC MADE (CONC = 0.0)
DWASH=NO MEANS NO BUILDING DOWNWASH USED
DWASH=HS MEANS HUBER-SNYDER DOWNWASH USED
DWASH=SS MEANS SCHULMAN-SCIRE DOWNWASH USED

DWASH=NA MEANS DOWNWASH NOT APPLICABLE, $X < 3 \cdot LB$

```
*****
*  SUMMARY OF TERRAIN HEIGHTS ENTERED FOR  *
*  SIMPLE ELEVATED TERRAIN PROCEDURE      *
*****
```

TERRAIN HT (M)	DISTANCE RANGE (M) MINIMUM	MAXIMUM
0.	10.	300.

```
*****
*** SUMMARY OF SCREEN MODEL RESULTS ***
*****
```

CALCULATION PROCEDURE	MAX CONC (UG/M**3)	DIST TO MAX (M)	TERRAIN HT (M)
SIMPLE TERRAIN	12.34	76.	0.

```
*****
** REMEMBER TO INCLUDE BACKGROUND CONCENTRATIONS **
*****
```

Interim 1-Hour NO ₂ Screening Background Concentrations in micrograms per cubic meter (µg/m ³) ¹			
Region / Specific County ²	Screening Background	Region / Specific County	Screening Background
1	70	10	70
		Jefferson	90
		Orange	70
2	70		
3	70	11	70
		Travis	85
4	70	12	70
Dallas	104	Brazoria	75
Ellis	85	Galveston	75
Tarrant	107	Harris	120
		Montgomery	75
5	70	13	70
Titus	90	Bexar	100
Rusk	90		
6	70	14	70
El Paso	124	Nueces	90
7	70	15	70
		Hidalgo	100
8	70	16	70
		Webb	100
9	70		
Freestone	90		
Limestone	90		

These values are conservative and based on available ambient monitoring design values (2007-2009) and may change as more research is conducted and/or data obtained.

If a value is too conservative, contact the Air Dispersion Modeling Team to determine if a more refined background concentration is available.

¹ Use the value for the region the project will be located in, or county if listed

² NAAQS in 188 µg/m³ converted from parts per billion based on standard temperature and pressure